


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

17-33-11W

Company- GULF OIL CORPORATION
 Farm- W. A. Newkirk No. 1

SEC. 17 T. 33 R. 11W
 CS $\frac{1}{2}$ SE NE SE
 986 SNL & 330 WEL SE $\frac{1}{4}$

County Barber
 KANSAS



Total Depth. 4855 P.B. 4588
 Comm. 5-4-54 Comp. 6-6-54
 Shot or Treated.
 Contractor.
 Issued. 8-28-54

CASING:
 10 3/4" 207 com. w/200 sx.
 7" 4630 com. w/150 sx.

Elevation. 1121 D.F.

Production. Pot. 276 bbls.

Figures Indicate Bottom of Formations.

red bed	207
red bed, shells	715
shale, shells, redbed	1255
shale, shells	1550
shale, shells, salt	1680
shale w/anhyd.	1785
shale, shells	1945
shale, shells, lime	2065
shale, lime	2550
shale	2670
shale, lime	3295
shale	3410
shale, lime	3620
shale, sand	3650
shale, lime	3689
Douglas sand	3700
sand	3715
sand, shale	3773
lime	4455
Miss. lime	4475
lime	4505
Miss. lime	4535
lime	4635
lime, shale	4760
lime	4855
Total Depth P.B. 4588	

Tops:	
Heebner	3585
Douglas shale	3660
Douglas sand	3689
Lansing	3787
Mississippian	4445
Kinderhook	4638
Chattanooga	4725
Viola	4758
Simpson	4853

Perf. 4490-4498 w/32 shots
 Perf. 4508-4532 w/96 shots

Treated w/500 gals. MCA followed by 6100
 gals. oil, 11,000 $\frac{1}{2}$ sand.

Sand record: Miss. lime (Perf 4490-4532)