

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


17-33-11W

Company- GULF OIL CORPORATION
 Farm- W. A. Newkirk No. 4

SEC. 17 T. 33 R. 11W
 NW SW SE

Total Depth. 4595; PB 4540
 Comm. 8-6-54 Comp. 8-29-54
 Shot or Treated.
 Contractor.
 Issued. 3-19-55

County Barber KANSAS



CASING:

Elevation. 1399 DF

8 5/8" 210' cem /w 150 sx Left in
 5 1/2" 4574' cem. w/150 sx Left in

Figures indicate Bottom of Formations.

Production. State Drawdown test
 1132 bbls . oil
 & NW

sand & redbed	213
redbed	275
redbed, shale & shells	1025
shale & shells	1435
shale, shells, salt	1505
Anhydrite	1565
shale & shells	1630
Anhydrite & shale	1700
shale & shells	1910
shale & lime	2040
shale & shells	2145
shale	2320
shale & lime	2665
shale	2850
shale & lime	3010
lime	3105
lime & shale	3255
shale	3335
shale & lime	3465
shale	3580
shale & lime	3655
sand & shale	3750
lime	3950
lime & shale	4085
sand	4110
lime & shale	4150
lime	4300
lime & shale	4380
lime	4435
cherty lime	4455
lime	4481
lime & chert	4517
lime	4570
lime & shale	4595
Total depth; PB	4540

Tops:
 Heebner 3560
 Douglas 3665
 Lansing 3752
 Miss. lime 4425
 Northview 4575
 Compton 4586

Remarks: Perf. 4474-4500' w/104 shots-
 treated w/420 gals. MCA, followed 2/
 6062 gals. oil,
 11,574# sand.
 Daily Allowable 37 bbls.
 Sand Record: Miss. lime (Perf. 4474-4500')