

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

17-33-11W

Company- GULF OIL CORPORATION
Farm- W. A. Newkirk No. 6

SEC. 17 T. 33 R. 11W
C SE SE SE

Total Depth. 4630

Comm. 9-19-54

Comp. 10-10-54

Shot or Treated. Perf. 4500-30 120 sh., 420 gal MCA, 13500 gal oil,


Contractor.

12500 # sand

issued. 1-8-55

County Barber

KANSAS



Elevation. 1431 DF

8 5/8 @ CASING: 208' w/ 150 sx cmt.
5 1/2 @ 4603' w/ 150 sx cmt.

Production. 502 BO, trace wtr

Figures Indicate Bottom of Formations.

surface clay & sand	50
red bed & shells	213
red bed, shale & shells	1080
shale, shells & salt	1480
anhydrite	1510
shale & lime	1885
lime	2000
lime & shale	2290
shale & shells	2525
shale	2760
shale & lime	2895
lime	3300
shale & lime	3365
shale	3660
lime & shale	3740
lime	4262
broken lime	4325
lime	4455
lime & chert	4495
lime	4619
shale & lime	4630
Total Depth	

TOPS:

Heebner	3590
Douglas	3711
Brown lime	3783
Lansing	3792
Mississippi lime	4455