

17-33-11W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GULF OIL CORPORATION
Farm-W. A Newkirk No. 8

SEC. 17 T. 33 R. 11W
SE SE SW
340' NSL & 2970' WEL

Total Depth. 4590 ; PB 4551
Comm. 10-10-54 Comp. 11-8-54
Shot or Treated.
Contractor.
Issued. 1-29-55

County Barber
KANSAS



CASING:

Elevation. 1394 DF

8 5/8" 235' cem. w/150 sx Left in
5 1/2" 4587' cem. w/150 sx Left in

Figures Indicate Bottom of Formations.

Production. 299.52 bbls. oil &
24.96 bbls. wtr
(Based on 99.84 oil, 832. wtr in
8 hrs.)

sand	65
redbed	95
redbed & shale	235
shale	1510
Anhydrite	1560
shale & shells	1635
Anhy. & shale	1775
lime & shale	2240
shale	2585
shale & shells	2870
shale & lime	3140
lime	3275
lime & shale	3335
lime	3415
shale & lime	3825
lime	3970
lime & shale	4030
lime	4385
lime & shale	4506
lime & chert	4527
lime	4590

Total depth; PB 4551

Tops:

Heebner shale	3552
Douglas sandstone	3659
Lansing group	3745
Miss. lime	4408
Northview shale	4566
Compton limestone	4578

Sand Record: Miss. (Perf. 4472-4482)
Distance H: 11' from RKB to top of 8 5/8"
csghead flange.
Perf. 4472-4482 w/40 shots-treated w/
200 gals. NCA, then 4500 gals. oil,
4500# sand.