

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


24-33-11W

Company- THE CARL TODD DRILLING COMPANY
Farm- Burns "A" No. 1

SEC. 24 T. 33 R. 11W
NE NE NE

Total Depth. 5161
Comm. 11-11-52 Comp. 12-7-52
Shot or Treated.
Contractor.
Issued. 1-3-53

County Barber KANSAS



CASING:
10 3/4" 240' cem. w/175 sx

Elevation. 1503 DE

Production. Dry

Figures in Feet from Formations.

red clay, gyp	40	DST: 4543'-4552' weak blow
red clay, gyp	100	for 20 mins. then intermittant
red bed, shells	860	open 1 hr. rec. 15' mud, no
shale, shells	1250	shows. BHP 52# in 10 mins.
shale, sand, lime	1550	DST: 4553-4567' gas in 3 mins.
lime, shale	1730	est. 500 MCF open 1 1/2 hr.s rec.
lime, salt	1850	30' rotary mud BHP 1665#
lime, shale	2070	
lime	2140	
lime, shale	3350	
lime	3392	
shale, lime, sand		
strks	3455	
lime, shale	3560	
shale	3640	
lime, shale	3780	
shale	3855	
lime	4150	
lime, shale	4230	
lime	4380	
shale, lime	4515	
shale, chert	4552	
chert	4590	
lime	4611	
chert	4613	
lime cherty	4725	
lime, chert	4741	
lime, shale cherty	4782	
shale, lime	4900	
viola, shale	4915	
viola	4943	
lime, chert	4985	
lime	5020	
shale, lime	5065	
shale	5090	
shale, sand	5136	
arbuckle	5161 RTD	
Total Depth		

Tops: RB

Elgin	3508
Heebner	3639
Toronto	3662
Douglas Fm.	3687
Douglas Sand	3692
Lansing	3855
Kansas City	4145
Base-Kansas City	4373
Mississippian	4541
Kinderhook	4783
Chattanooga	4853
Misener	4881
Sylvan	4886
Viola	4899
Simpson	4992
Arbuckle	5136