

26-33-11W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY TENNECO OIL CO. & BURCH EXPLORATION CO.
FARM Bowers NO. 1

SEC. 26 T. 33 R. 11W
LOC. C NW NE

TOTAL DEPTH 4740'
COMM. 11-23-65 COMP. 12-9-65
SHOT OR TREATED
CONTRACTOR Burch Exploration Co.
ISSUED 7-2-66

COUNTY Barber

KANSAS



CASING

20	10	
15	8 5/8	253' w/200 sx cem.
12	6	
13	5	

ELEVATION 1486' KB

PRODUCTION DRY

FIGURES INDICATE BOTTOM OF FORMATIONS

290 Red Bed
600 Red Bed & Shale
820 Shale
1680 Shale & Shells
4025 Lime & Shale
4310 Lime
4370 Lime & Shale
4740 Lime

4740 Rotary Total Depth

Tops

Heebner	3636 (-2160)
Lansing	3848 (-2362)
Mississippi	4534 (-3048)
Porosity Zone (Sc)	4540-90

DST #1. 4538-4580. 10 minute preflow;
tool open total of one hour; gas to surface
in 36 minutes; recovered 260' gas cut mud.
IBHP 870# (45 mins); IFP 68#; FFP 102#;
FBHP 1382# (1 hr.)

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Earl M. Burch, President of Burch Exploration, Inc. being duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Earl M. Burch, President

Subscribed and sworn to before me this 15th day of December, 1965.

Minnie E. Matson, Notary Public