

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey

API No. 15 - 007 County


21,024 Number WICHITA BRANCH

S. 26 T. 33S R. 11 W

Loc. C S/2 SW SE

County Barber

640 Acres N



Locate well correctly

Elev.: Gr. 1454'

DF 1456' KB 1458'

Operator
Hawkins Oil & Gas, Inc.

Address
320 So. Boston Bldg., Suite 701, Tulsa, OK 74103

Well No. 1-26 Lease Name MONTGOMERY

Footage Location
330' feet from (S) line 1980 feet from (E) line

Principal Contractor DNB Drilling, Inc. Geologist Kory Boster

Spud Date 11-5-80 Date Completed 11-25-80 Total Depth 4623' P.B.T.D. 4573'

Directional Deviation N/A Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	342'	common	250	2% gel, 3% CC
Production	7 7/8"	4 1/2"	10.5#	4623'	Class "H"	50	8% gel, 10% salt 12 1/2# gilsonite
					50/50 poz.	150	18% salt, .75% CFR-2 12 1/2# gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1 SPF	.38" dia.	4555-4559'
TUBING RECORD			"		4566-4571'
Size	Setting depth	Packer set at	"		4576-4578'
2 3/8"	4530'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gals. 15% MCA	4555-4578'
Cement retainer set @ 4573'	

INITIAL PRODUCTION

CONSERVATION DIVISION
Wichita, Kansas

Date of first production Shut in WO GSC Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS
Oil trace bbls. Gas 870 MCF Water 0 bbls. Gas-oil ratio ---- CFPB

Disposition of gas (vented, used on lease or sold) to be sold Producing interval (s) Mississippi Chat.

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note 'e 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Gas

for
Hawkins Oil & Gas, Inc.

Well No.

1-26

Lease Name

MONTGOMERY

S 26 T.33S R 11 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

Logs Run

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Lime and shale	0'	3903'		
Lime and shale	3903'	4381'	Lansing/KC	
Lime and shale	4381'	4538'		
Lime, sand and shale	4538'	4553'	Cherokee	
Lime and chert	4553'	4628'	Mississippian	
TD	4628'			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Kathy B. McGuire
Signature

Kathy B. McGuire/ Hawkins Oil & Gas, Inc.

Title

March 12, 1981

Date

26 - 33 - 91W

DRILLER'S LOG

State Geological Survey
WICHITA, BRANCH

HAWKINS OIL & GAS, INC.
No. 1-26 Montgomery
330' FSL & 1980' FEL
Sec. 26-33S-11W
Barber Co., Ks.

Commenced: 11-14-80
Completed: 11-25-80

Surface Casing: 340' of 8-5/8
cemented w/250 sx common, 2% gel,
3% cc

FORMATION

DEPTH

Surface Hole	0 - 342
Lime	342 - 400
Shale & Lime	400 - 739
Sand & Shale	739 - 1038
Shale & Lime	1038 - 1877
Lime & Shale	1877 - 2122
Shale & Lime	2122 - 2263
Lime & Shale	2263 - 2662
Shale & Lime	2662 - 2854
Lime & Shale	2854 - 3203
Shale & Lime	3203 - 3596
Lime & Shale	3596 - 3714
Shale & Lime	3714 - 4140
Lime	4140 - 4380
Lime & Shale	4380 - 4438
Lime	4438 - 4569
Lime & Sand	4569 - 4623 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 26th day of November, 1980.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

