

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


30-33-11W

Company- SKELLY OIL CO.
Farm- Felix Fitzgerald No. 1

SEC. 30 T. 33 R. 11W
SE SE NE

Total Depth. 4630' PB 4588'
Comm. 3-25-54 Comp. 4-10-54
Shot or Treated.
Contractor. Chas. Hulme Drlg.
Issued. 7-3-54

County Barber
KANSAS



CASING:

8 5/8" 397' cem w/225 sx
5 1/2" 4576' cem w/150 sx

Elevation. 1120' DE

Production. 45 B0 & 21 BW
in 24 hrs.

Figures indicate Bottom of Formations.

red bed, shale & shells	397
shale and shells	1550
lime	1585
shale and lime	1980
lime	2195
lime and shale	2395
shale and shells	2735
shale	2855
shale and shells	3000
shale and lime	3710
lime	4550
cored	4610
cored	4630
Total Depth	Plugged back to 4588'

Tops:

Elgin Sand	3494
Heebner Shale	3624
Douglas	3657
Lansing Lime	3804
Base Kansas City Lime	4360
Marmaton	4386
Mississippi Lime	4506

Ran Schlumberger Survey

Cored from 4550' to 4610' Recovered 43'
Cored from 4610' to 4630' Recovered 20'

4-14-54, Shot 4576-4630' Sand-Oil-Frac
Put in by Halliburton
5-28-54, Shot 4576-4588' Sand-Oil-Frac
Put in by Halliburton

Producing Formation Mississippi Lime 4576 to 4588'