

31-33-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- Honaker-Davis Drlg. Co.,
Farm- Newkirk No. 1

SEC. 31 T. 33 R. 11W
NE NE SW

Total Depth. 5060'
Comm. 7-20-57 Comp. 8-9-57
Shot or Treated.
Contractor. Honaker-Davis Drlg. Co.,
Issued. 11-16-57

County Barber KANSAS



Elevation. 1163 R. B.

Production. 45 BOPD & 15,500,000
CFG.

CASING:

8 5/8" @ 217' W/200 sks. cem.
5 1/2" @ 4714' W/150 sks. cem.

Figures Indicate Bottom of Formations.

top soil	30
shale, shells & red bed	217
red ved, shale & shells	435
shale & shells	775
shale & Gypsum	1015
shale & shells	1580
shale, lime & shells	1635
shale & lime	1795
lime & shale	1925
lime	2155
shale with lime	2265
lime & shale	2420
shale	2755
shale & lime	2855
lime & shale	3305
shale & lime	3580
lime & shale	3795
shale & lime	3880
lime & shale	3950
lime	5060
Total Rotary Depth	5060

Tops:	
Heebner	3668
Lansing-Kansas City	3868
Mississippian	4561
Kinderhook	4798
Viola	4914
Simpson	5025

Drill Stem Tests:

#1 4557-4587, Johnston testers, Tool
open: 20"-60"-20" Blow: 660,000 CFG.
Rec: 115' GCM. Pressures: IBHP
1830#, FBHP 1645#, IFP 140#, FFP 130#,

#2 4587-4610, Johnston testers Tool
open: 20"-60"-20" Blow: Gas to
surface 15" Rec: 50' GCM. Pressures:
IBHP 1770#, FBHP 1385#, IFP 30#, FFP
35#,

#3 4610-4650 Johnston testers Tool open:
20"-30"-20" Blow: 3,000,000 CFG Rec:
80' SO & GCM Pressures: IBHP 1845#,
FBHP 1800#, IFP 470#, FFP 480#,

