


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- Forester No. 1

SEC. 34 T. 33 R. 11W
SE NW NW

Total Depth. 4850 PBSD 4518
Comm. 4-6-54 Comp. 8-11-54
Shot or Treated.
Contractor. Anschutz Drilling Co., Inc.
Issued. 11-6-54

County Barber
KANSAS



Elevation. 1384 DF

CASING:

10 3/4 @ 320' w/ 250 sx cmt.
7 in. @ 4812' w/ 200 sx cmt.

Production. Shut in gas well.

Figures Indicate Bottom of Formations.

sand rock	40	Sandoilfrac. Sq perf 4480-4518 &
sand, rock & shale	325	4524-50. Drld cmt to 4500. Perf
shale & shells	1050	4480-4500 w/ 80 %. Sandoilfrac
salt	1125	Swb & fl. 160 BLO minus 74 BLO.
shale & lime	1650	F 3 1/2 BW, no oil 6 hrs. Est 500,000
lime	1740	CFGPD on 1" ck.
shale & lime	2960	
lime	3230	
shale & lime	3721	
sandy shale	3781	
lime	3992	
lime & shale	4062	
lime	4440	
Mississippi lime	4705	
shale & lime	4735	
shale & shells	4805	
shale & lime	4815	
Viola lime	4850	
Total Depth		

TOPS:

Elgin sand	3444
Heebner	3556
Douglas sand	3621
Lansing	3775
Mississippian	4479
Kinderhook	4677
Misener sand	4806
Viola	4815

DST #1: 4479-4524, open 1 hr. SI 30 min.
gas in 3 min. ga 416,000 CFGPD 1 hr.
rec. 95' GCM, IFP 88#, FFP 105#,
BHP 1780#

DST #2: 4524-84, open 1 hr. SI 30 min.
weak blow thruout, rec. 40' mud w/
tr. oil specks, IFP 54#, FFP 72#,
BHP 105#

DST #3: 4588-4652, open 1 hr. SI 30
min. weak blow thruout, rec. 50' oil
specked mud, IFP 42#, FFP 55#, BHP 136#

PB 4778, perf 4610-50 w/ 160 %. Sand-
oilfrac. Est. 1,000,000 CFGPD, F 70 BF
40% SW, 24 hrs. PB 4602, perf 4560-90
w/ 120 %, Sandoilfrac. F 158 BLO & 45 BW
11 hrs. on 1" ck. F 81 BBS & 205 BSW on
1" ck. Sq. perf. PB 4555 perf 4524-40
w/ 72 %, Sandoilfrac. Acidized w/ 1000
gals. F load oil & 4 BNO & 5 BW 24 hrs.
Perf 4540-50 w/ 40 %. Sandoilfrac perf
4524-50 F load oil & 4 BNO & 30 BW 24
hrs. PB 4518, perf 4480-4518 w/ 152 %
gas broke thru F @ rate 2,600,000 CFGPD.