


MAP NO. _____ ELEV. 1898 DF
 STATE Kansas COUNTY Clark SEC. 11 Twp 33 S Rge 22 W
 OPERATOR Sunray Mid-Continent Oil & Petroleum, Inc. LOC. C SE/4
 WELL NO. 1 FARM NAME A. R. Baker FT. FROM _____ LINE _____
 POOL Sitka (PD 5450) FT. FROM _____ LINE _____
 FR. 6-30-61 SPUD 7-6-61 COMP. 9-20-61

CONT./GEOL. Garvey Drilling

COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a. <u>Morrow</u>	<u>5222-70</u>	<u>108</u>	<u>750A-F/10X16</u>
b. _____	_____	_____	_____
c. _____	_____	_____	_____
d. _____	_____	_____	_____



I. P. OIL/DIST.	WTR.	GOR.	GAS	M.C.F.P.D.	CHK.	HRS.
a. _____	_____	_____	_____	_____	_____	_____
b. _____	_____	_____	_____	_____	_____	_____
c. _____	_____	_____	_____	_____	_____	_____
d. _____	_____	_____	_____	_____	_____	_____

SICP 1678 SITP 1689 D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT. 5275 TD 5410

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD - SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>605</u>	<u>375</u>	_____	_____	_____
<u>4 1/2"</u>	<u>5409</u>	<u>cem</u>	_____	_____	_____

OPERATOR Sunray M-C & Pet Inc WELL NO. 1 A. R. Baker ELEV. 1898 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	4173		Elgin	4018	
Douglas	4235		Heebner	4169	
Lansing	4389		Toronto	4207	
Marmaton	4951		Lansing	4386	
Cherokee	5096		Cherokee	5070	
Mississippian	5283		Morrow	5216	
			Morrow Sand	5240	
			Morrow Sand	5250	
			Chester	5283	

5216
 1900
 -3316
 1900
 33

Spud 7-6-61. 8-5/8" @ 605 w/375 sx.
 DST # 1 failed.
 DST # 2 (Cherø & Miss) 5220-5309, op 1 hr, GTS 3 mins, ga 1020
 MCF/5 mins, stable @ 1250 MCF/10 mins, rec 210' GCM, ISIP
 1993/60 mins, FP 333-321, FSIP 1894/60 mins.
 RTD 5410, logs to 5409. 4 1/2" @ 5409 w/cem. MICT.
 P/60/5284-5314 Swb ld/NS. 1000 Ac. Swb ld/SSG. 10,000 Ac.
 Swb 4 FAWPH/SSG. SQ 5284-5314 w/cem. CO ro 5275.
 P/56/5222-36 28/5239-46, 8/5252-54, 16/5266-70. Ga 500 MCF.
 750 Ac. Swb ld. Ga 500 MCF. Frac 10,000 Ac X 16,000 sd.

A 9-246

SHEET NO. 2

MAP NO. _____

STATE Kansas COUNTY Clark SEC. 11 Twp 33 S Rge 22 W

OPERATOR Sunray Mid-Continent LOC. C SE/4

WELL NO. 1 FARM NAME A. R. Baker

Set tbg @ 5186. Ga 1450 MCF w/3/4 BDPD, 22/64" ck, FTP 940,
FCP 800. Ga 1250 MCF + 6 BD + 18 BLW/24 hrs, 1/2" ck, FTP 200,
FCP 800 (lack 242 BL). Ga 734 MCF/tr dist/14 hrs, 17/64" ck,
TP 860, CP 1020.

IP COF 1060 MCF, SICP 1678, SITP 1689, FCP 911, FTP 862, del
516 MCF on 80% SIP from Morrow (5222-70).

COMPLETE 9-20-61

OPERATOR

WELL NO.