

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

4-33-12W

Company-SKELLY OIL CO.
Farm-Boggs "J" No. 1

SEC. 4 T. 33 R. 12W
SE NW NW
990' fr NL 990' fr WL NW/4

Total Depth. 4558 PBTB 4521
Comm. 8-23-55 Comp. 9-6-55
Shot or Treated Perf. 198/4474-4507, 500 gal acid & San-Oil-Frac
Contractor. Chas. Hulme Drilling Contractor 4474-4507
Issued. 2-4-56

County Barber
KANSAS



CASING:
8 5/8 @ 346' w/ 225 sx cmt.
5 1/2 @ 4556' w/ 150 sx cmt.

Elevation. 1632 DF

Production. 6,210,000 CFGPD

Figures indicate Bottom of Formations.

surface soil, gyp & clay	193
red bed, shale & shells	346
red bed & shells	705
shale & shells	885
shale, salt & shells	1590
lime	1800
lime & shale	1920
lime	2070
lime & shale	2175
lime & sandy shale	2285
lime	2430
shale & lime	2665
shale	2840
shale & lime	3110
lime	3470
shale	3530
lime & shale	3640
lime & sandy shale	3740
shale & sand	3880
sand	3918
lime	4478
chert	4480
light opaque tripolitic chert	4492
light opaque tripolitic	
chert w/ green & gray shale	4495
chert	4513
chert & lime	4558
Total Depth	

Plugged back to 4521

TOPS:
Heebner 3721
Ireland 3733
Tonganoxie sand 3872
Brown lime 3916
Lansing 3925
Base K. C. 4399
Marmaton 4419
Mississippi lime 4474

DST #1: packer @ 4468, 45' anchor,
open 1 hr. strong blow air immed.
gas to surf. 4 min. gauged 416 MCF
rec. 120' GCM, IFP 80#, FFP 80#,
BHP 1632#/20 min.

Ran Schlumberger Survey

Producing Formation: Mississippi,
4474-4507