


Company - SKELLY OIL CO.  
Farm - Boggs "D" No. 2

SEC. 5 T. 33 R. 12W  
CSW NW  
660' fr S.L. 660' fr W.L. of  
NW/4

Total Depth. 5067  
Comm. 3-28-51 Comp. 4-30-51  
Shot or Treated.  
Contractor. Chas. Hulme Drlg. Co.  
Issued. 7-7-51

County. Barber

KANSAS



CASING:  
8 5/8" 423' cem. w/250 sx

Elevation. 1664 ft  
1665 RB (and)

Production. Dry

Figures Indicate Bottom of Formations.

surface soil & shale	175	Viola Lime	4808
red bed, shale & shells	423	Simpson Shale	4906
shale & red bed	1000	Simpson Sand	4916
salt	1080	Arbuckle Lime	5004
shale	1460	Show oil & gas saturation	
lime & shale	1530	3865-3869'	
shale & shells	1900	Ran Halliburton drill stem	
lime	2065	test, packer set at 3866',	
lime & shale	2225	used 14' anchor, gas to surface	
sandy lime	2270	in 2 mins. gas gauged 210 M.C.F.	
shale	2290	Tool open 1 hr. rec. 1500' salt	
shale & lime	3050	wtr. and 4' of free oil, BHP	
lime	3425	1200#.	
lime & shale	3750	4523-28' spotty black oil	
shale	3785	stain and saturation, porosity	
shale & lime	3865	very poor.	
medium grained porous		No porosity 4805-4895	
sand	3869	No shows 4954-4960'	
sand & shale	3880	Ran Halliburton drill stem	
shale & lime	3907	test, packer set at 4900',	
sand	3945	open 40 mins, rec, 12'	
lime	4415	of drilling mud, no BHP.	
lime & shale	4480	No shows 5004-5052'	
lime	4500	No shows 5052-5067'	
lime & chert	4523	Spotted fresh mud from 5067'	
lgt gry cherty lime with		to 3500' and ran Schlumberger	
lgt porosity & spotted		Survey.	
oil stain	4527		
lime	4645		
chert	4672		
lime	4700		
lime & shale	4730		
shale	4795		
lime & sand	4805		
very tight dolomite	4895		
lime	4912		
stringers of sand & shale	4954		
gry medium grained very			
lgt sand	4960		
shale with thin scattered			
sand streaks	4970		
sand	4985		
sand & shale	5004		
fine granular to fine			
medium xyln slightly			
porous dolomite	5052		
fine to medium xyln sandy			
dolomite	5067		
Total Depth			
Tops:			
Tonganoxie Sand	3866		
Lansing Lime	3964		
Mississippi Chert	4525		
Red Zone	4545		
Kinderhook	4700		
Misener	4806		