

8.33.12W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - SKELLY OIL CO.
Farm - Alexander-Boggs Unit No. 1

SEC. 8 T. 33 R. 12W
NE NE NW
330' fr NL, 390' fr EL NW/4

Total Depth. 3775
Comm. 12-16-48 Comp. 12-31-48
Shot or Treated.
Contractor. Chas. Hulme Drilling Co., Tulsa, Oklahoma
Issued. 6-11-49

County. Barber

KANSAS



Elevation. 1560 *and*

Production. Open Flow 134,800,000
gas

Figures Indicate Bottom of Formations.

surface soil, red bed,	
shale, shells	220
red bed, shells	455
red bed	565
red bed, shale, salt	1290
shale, shells	1600
shale, lime	1650
lime	1860
lime, shale	1960
lime	2420
lime, shale	2560
lime	2640
lime, shale	2870
lime	3155
lime, shale	3285
lime	3320
lime, shale	3630
lime	3675
shale, sand	3742
sand wht, fine grained	
tight	3745
sand wht med grained	3760
same formation	3775
Total Depth	

Tops:

Douglas Sand	3742
Tonganoxie Sand	3760

Gas from 3760 to 3775'.
Producing Formation: Tonganoxie Sand.
3760- slightly porous
3775- fair to good porosity.
Ran DST w/packer set at 3746', open
5 mins, recovered 800' of drilling
mud, gas gauged 6,352 MCF.
Open Flow Test May 2, 1949 showed
well making 134,000,000 gas.