

9-33-12W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas


Company - MAGNOLIA PETROLEUM COMPANY
Farm - Boggs Estate No. 1

SEC. 9 T. 33 R. 12W
SW SW SW

Total Depth: 4891 K.B.
Comm. 2-9-48 Comp. 3-24-48
Shot or Treated.
Contractor. Barnett Drlg. Co.
Issued. 12-3-49

County. Barber

KANSAS



Elevation. 1564' sand

CASING:
8" set @ 1694' w/800 sx.
5" set @ 4863' w/250 sx.

Production. 65 BO
1,780,000 CFG

Figures Indicate Bottom of Formations.

Clay	10
Shale & shells	410
Red bed	525
Shale	750
Shale & shells	850
Shale	860
Shale & shells	1185
Shells	1255
Shale, shells & salt	1440
Shale & shells	1580
Salt & shale	1660
Lime	2045
Lime & shale	2100
Lime	2235
Lime & shale	2650
Shale	2700
Lime & shale	2840
Shale & lime	3040
Lime	3182
Lime & shale	3220
Lime	3365
Lime & shale	3425
Shale	3560
Shale & lime	3635
Shale	3685
Lime & shale	3965
Lime	4035
Lime & shale	4082
Lime	4107
Lime & shale	4145
Lime	4365
Lime & shale	4456
Lime	4490
Shale & lime	4515
Lime & shale	4740
Lime	4764
Lime & shale	4784
Shale & lime	4836
Cored sand & shaly sd.	4872
Sand & shale	4891

DST 4466-76, op. 30 mins. rec. 55' rotary mud.
DST 4863-73, op. 30 mins. rec. 260' oil, BHP 1360#.
Cored 4836-54, rec. 16' sandy shale
4854-72, rec. 11' sandy shale, 7' oil sat. sand.

Total Depth

FORMATION TOPS:

Lansing	3678
Miss.	4465
Viola	4741
Simpson	4836