


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER-DAVIS DRILLING COMPANY, ET AL
Farm- Ives No. 1

SEC. 10 T. 33 R. 12W
SW SE NE

County Barber KANSAS

Total Depth. 4920'
Comm. 10-27-56 Comp. 11-18-56
Shot or Treated.
Contractor. Honaker-Davis Drilling Company
Issued. 4-20-57



Elevation. 1451' RB

Production. Dry

Figures indicate Bottom of Formations.

- surface soil 40
- shale & shells 190
- red bed & shale 580
- shale, red bed, Gypsum 825
- shale & shells 1330
- Anhydrite 1360
- shale & shells 1495
- lime & shale 2425
- shale 2530
- shale & lime strks 2715
- shale & lime 3739
- shale & sand 3743
- lime & shale 3900
- lime 4158
- lime & shale 4214
- lime 4515
- shale & lime 4676
- lime 4750
- lime & shale 4771
- lime 4920 RTD

Total Depth

- TOPS
- Heebner 3596
- Lansing/Kansas City 3768
- Mississippian 4362
- Kinderhook 4555
- Viola 4658
- Simpson 4762
- Arbuckle 4900

DRILL STEM TESTS

DST #1
3731-3743 (Douglas Sand)
Halliburton Tool op. 60"
closed 30# Blow weak,
Rec. 90' SW Pressure:
BHP 1265# FFP 48#.

DST #2
4346-4370 Halliburton
Tool op. 60" closed 20"
Blow Fair Rec 20' WCM
Pressure: BHP 205#
IFP 15# FFP 15#

DST #3
4761-4768 Halliburton
Tool op. 60" closed 20"
Blow, good Rec. 300'
gas 65' O & GCM, 60'
O C M W 60' water,
Pressures: BHP 1702#
IFP 30# FFP 90#

