

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Plotted
16-33-12W

Company - CITIES SERVICE OIL COMPANY
Farm - Boggs "B" No. 2

SEC. 16 T. 33 R. 12W
SW NW SW
990' S & 330' E of W/4 corner

County. Barber
KANSAS

Total Depth. 4903' SIM

Comm. 2-14-47
Shot or Treated.

Comp. 3-4-47


Contractor. R.W. Rine Drilling Co.

Issued. 5-24-47

CASING:

8-5/8" 530' Cem. w/300 sx
5-1/2" 4875' Cem. w/300 sx

Elevation. 1543 set



Production. BHP Gauge Pot: 943
oil, no wtr, 24 hrs.

Figures Indicate Bottom of Formations.

cellar	0-8
red rock & shale	135
red bed & shells	500
red bed	530
red bed & shells	835
shale & shells	1620
shale & lime	3933
lime	4186
lime & shale	4341
shale	4372
lime & shale	4464
lime	4495
lime & shale	4725
shale	4750
lime	4756
lime & shale	4805
lime	4828
lime & dolomite	4849
shale & lime	4861
shale & sand	4880
lime & shale	4903
4903 RTD=4903 SIM	
Total Depth	4903 SIM

Tops:

Lansing	3886
Mississippi	4435
Viola	4750
Simpson Shale	4848
Simpson Sand	4878
Penetration	25

BHP Gauge Potential: 943 oil,
no wtr, 24 hrs.

BHP 1932 $\frac{1}{11}$

Gas-oil ratio 295/1