


16 33-12W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Boggs "B" No. 4

SEC. 16 T. 33 R. 12W
SW 1/4 NW
330' N & 330' E of W 1/4 corner

County. Barber
KANSAS



Total Depth. 4835'
Comm. 5-14-47 Comp. 6-4-47
Shot or Treated. None
Contractor. R. W. Rine Drilling Co.
Issued. 1-20-47

CASING:

8-5/8" 535' com. 300 sx. com.

Elevation. 1475 set & rh

Production. None Dry Hole

Figures Indicate Bottom of Formations.

surface hole	0-320
red rock & shale	535
shale & shells	1670
lime & shale	1825
lime	1940
lime & shale	2410
shale	2425
lime & shale	2660
shale & lime	2705
lime & shale	3285
lime	3355
lime & shale	3525
shale & lime	3608
lime & shale	3793
sand	3801
shale	3814
lime & shale	4119
lime	4131
lime & shale	4206
lime	4243
lime & shale	4492
shale	4525
lime & shale	4600
shale	4671
lime	4713
shale & lime	4733
lime & shale	4800
sand & shale	4835
sand & lime	4835 T. D.

TOPS:

Lansing	3815
Mississippi	4398
Viola	4669
Simpson shale	4767
Simpson Sand	4775
Penetration	60
Total Depth	4835

Drill stem test 4780-4825, recovered
60' mud in 30 mins., no oil, no gas.

7-7/8" rotary hole.