

17-33-12W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL CO.
Farm - Boggs "C"

No. 1

SEC. 17 T. 33 R. 12 W
SW NE NE
990' fNL & 990' fEL NE $\frac{1}{4}$

Total Depth. 4844'

Comm. 5-8-46


Comp. 6-20-46

Shot or Treated.

Contractor. Ruso Drlg. Co.

Issued. 3-15-47

County. Barber
KANSAS



CASING:

10 3/4"
7"

427' Cem. w/200 sx.
4820' SLM Cem. w/200 sx.

Elevation. 1515 rh

Production. Pot. 45 BQ.
1,360,000G. after
shot.

Figures Indicate Bottom of Formations.

sand	0-90	sand dense gy, 25%	
shale & shells	427	shale green sdy, no	
shale & shells	1210	sat. 1200' OIH in	
lime	2020	24 hrs.	4835
lime sdy	2145	sand gy w/50% shale,	
lime	2335	no sat.	4838
shale & lime	2805	sand gy, sli. stain,	
limo	3085	no sat.	4843
lime & shale	3140	shale green, no inc.	
lime	3170	in gas	4844
lime & shale	3365	Total Depth.	
shale	3500		
lime	3605	Tops:	
shale & lime	3665	Mississippi Lime	4408
shale	3745	Viola Lime	4695
lime	3775	Simpson Dolomite	4802
shale	3860	Simpson Sand	4811 SLM
lime	4190		
lime & shale	4408		
chert gy & wh		4823-30' Good Por. & Sat.	
weathered, sli. por.		4838-43' Sli. Stain, no Sat.	
no sat.	4415		
chert gy & brwn		6-22-46 - Shot w/80 qts. 4842-24'	
w/little dense			
dolomite, hrd no			
sat.	4420		
chert gy & brwn			
w/little dense			
dolomite, no por.			
or sat.	4426		
lime	4450		
lime & shale	4555		
lime	4590		
shale & lime	4625		
lime	4685		
limo & shale	4695		
lime dense gy &			
dolomite w/little			
chert	4708		
lime dense gy & dolo-			
mite w/little chert,			
no por., stain or			
sat.	4735		

shale 4750
lime 4759
lime sdy 4780
lime 4802
dolomite gy finely
xlyn, no por. or
stain 4807
dolomite gy sdy, poor
por. & no sat. 4819
sand sft gy & brwn,
good por. & sat. 4826
sand hrd gy, no por.
or sat. 4827
Corr: 4827' SLM Rot.
table: 4831' SLM DP