

17-33-12W


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL COMPANY
Farm - Boggs "C" No. 6

SEC. 17 T. 33 R. 12W
SEc SW
330' fE1 & 330' fS1 SW $\frac{1}{4}$

Total Depth. 4885'
Comm. 7-29-47 Comp. 8-26-47
Shot or Treated.
Contractor. H and T Drilling Company
Issued. 10-11-47

County. Barber
KANSAS



CASING:
8-5/8" OD 1705' Com. w/800 sx
5-1/2" OD 4830' Com. w/200 sx

Elevation. 1526 sat & rh

Production. Phy. Pot.: 461 BO &
580,000 Gas

Figures Indicate Bottom of Formations.

surface soil & sand	0-100
red bed	840
shale & shells	1290
salt & shale	1515
shale & lime	1705
lime	2485
shale & lime	3315
shale	3595
lime & shale	3660
shale	3730
lime & shale	3900
lime	4085
lime & shale	4105
lime	4155
lime sdy	4195
lime	4210
lime & shale	4270
lime	4320
lime & shale	4440
lime cherty & shale	4475
lime & shale	4675
shale	4715
lime & shale	4740
lime & chert	4770
lime	4810
lime gy coarsely xlyn hrd	4826
dense gy dolomitic sand	4830
gy & brwn sand	4833
sand dense gy	4836
sand brwn friable	4850
sand gy & brwn	4859
shale sdy	4863
med. sft gy sand	4875
rand dense gy	4885
Total Depth	

limestone	3969
Mississippi lime	4438
Viola lime	4730
Gilpin Sand	4826

4830-4833 Sil. sat., medium hrd.
4833-4850 Porous and saturated.
4850-4859 Spotted por., sli. sat.
4859-4885 Sil. por., spotted oil stain.