

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


17-33-12W

Company - SKELLY OIL COMPANY
Farm - Boggs "C" No. 10

SEC. 17 T. 33 R. 12W
SE SE NW
330' fr E1 & 330' fr S1 NW $\frac{1}{4}$

Total Depth. 4870'
Comm. 7-17-48 Comp. 8-10-48
Shot or Treated. Acidized
Contractor. Overland Drlg. Co.
Issued. 1-22-49

County. Barber
KANSAS



CASING:

8-5/8" 1661' Cem. 1/780 Sx.
5-1/2" 4809' Cem. W/200 Sx.

Elevation. 1513.2nd.

Production. POB 8 hrs. 65 BO to
est. 24 hr. bot 195 Fbbls.
after acid.

Figures Indicate Bottom of Formations.

surface soil & red bed	155
red bed & shale	570
shale	700
shale & shells	1140
s. lt & shale	1250
shale & shells	1410
lime wh & shale	1445
shale & shells	1505
shale & red bed	1562
lime	2175
lime & shale	2630
shale	3025
shale & lime	3265
lime	3415
lime & shale	3610
shale	3690
lime & shale	3815
shale & sand	3861
lime	3840 ?
lime & shale	3955
shale	3970
lime	4310
shale	4355
shale & lime	4395
lime	4415
lime cherty	4430
shale	4465
lime & shale	4490
lime sdy	4520
shale & lime	4550
shale	4575
lime cherty	4600
lime & shale	4615
shale	4725
lime	4795
lime & shale	4809
non-porous sand	4813
shale dy	4819

Tops:

Lansing Lime	3845
Mississippi Lime	4414
Viola Lime	4717
Simpson Shale	4805
Simpson Sand	4809
4414-4419 sat. w/heavy oil	
4819-4825 slight stain & odor	
4843-4855 faint odor, lgt stain.	

sand, fine ls & possibly	
porous	4825
shale & sdy shale	4843
sand	4855
sand & shale sdy	4857
shale	4860
sand	4862
shale	4870
Total Depth	

Producing Formation: Simpson Sand 4819' 4825'
4843'-4855'

Acid. 8-31-48 W/120 qts 4864-4816'
4" shell collapsed 4800'