

17-33-12W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
Wichita, Kansas


Company - SKELLY OIL COMPANY  
Farm - Boggs "C" No. 11

SEC. 17 T. 33 R. 12W  
NW SW SE  
990' FSL 330' FWL SE/4

Total Depth. 4944  
Comm. 6-18-49 Comp. 7-17-49  
Shot or Treated.  
Contractor. Chas. Hulme Drilg. Co.  
Issued. 11-19-49

County. Barber

KANSAS



Elevation. 1591 ft

Production. 259 Bbls.

Figures Indicate Bottom of Formations.

Surface soil, red bed & sand	110
Lime & red bed	584
Shale & shells	1775
Lime & shale	2320
Lime	2440
Lime & shale	2515
Shale	2940
Lime & shale	3105
Shale & shells	3165
Shale & lime	3485
Shale & shells	3555
Lime & shale	3675
Shale	3760
Shale & lime	3865
Lime	3890
Sand (no shows)	3930
Lime	4075
Cherty lime	4105
Hard lime	4331
Lime & shale	4375
Lime	4398
Lime & shale	4475
Lime	4501
Chert	4510
Lime & chert	4595
Lime & shale	4671
Shale	4727
Shale & lime	4805
Shale	4835
Shale & lime	4856
Lime & chert	4888
Shale & sand	4890
Sand	4894
Sandy shale	4897
Sand	4904
Shale sandy	4906
Sand	4910
Shale	4912
Sand	4914
Shale	4916

FORMATION TOPS:

Douglas	3899
Lansing	3928
Miss.	4501
Kinder.	4651
Viola	4792
Simpson sh.	4889
Simpson sd.	4890

4897-4944 oil stained & saturated

Sand	4919
Sandy shale	4930
Sand	4943
Shale	4944
<b>Total Depth</b>	