

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- SKELLY OIL CO.
 Farm- Boggs "G" No. 20

SEC. 17 T. 33 R. 12W

ON $\frac{1}{2}$ SW NE
 990 f SL 660 f WL NE/4

Total Depth. 4868 P.B. 4833
 Comm. 1-21-55 Comp. 2-12-55
 Shot or Treated.
 Contractor. C. Wentworth Drilg. Co.
 Issued. 4-9-55

County Barber
 KANSAS



Elevation. 1524 D.F.

Production. pot. 167 bbls.

CASING:

8 5/8" 478 cem. w/275 sx.
 5 1/2" 4868 cem. w/200 sx.

Figures Indicate Bottom of Formations.

surface soil & red bed	30
red bed & shells	530
shale & red bed	610
red bed & shells	760
shale & shells	960
anhyd.	990
shale & shells	1655
lime & shale	1900
lime	2020
lime & shale	3255
lime	3430
lime & shale	3960
lime	4583
lime & shale	4622
lime	4665
lime & shale	4740
lime	4789
lime & shale	4811
Cored 4811-4813 $\frac{1}{2}$ Rec. 2 $\frac{1}{2}$ '	
Cored 4813 $\frac{1}{2}$ to 4868 Rec. 51'	
Total Depth P.B. 4833	

Tops:	
Heebner shale	3692
Tonganoxie sand	3824
Brown lime	3832
Lansing	3851
Base Kansas City	4334
Marmaton	4345
Mississippi	4422
Viola lime	4708
Simpson shale	4799
Simpson dolo.	4805
Simpson sand	4815

Producing form. Sim son sand 4824-4831

Oil 4824-4831

Ran Lane Wells Gamma Ray

D.S.T. packer set at 4813 used 55' anchor
 open 1 hr, gas to sur. in 2 mins, gas gauged
 396 M.C.F. at end of test, rec. 180' of free
 oil, 360 slightly gas cut muddy oil, 180'
 heavily oil & gas cut mud, and 120' of gas
 cut watery mud, init. flow 249#, FF 356#,
 BHP 900# in 20 mins.

2-19-55 Shot between 4341-4847
 Halliburton Viso-frac