

21-33-12W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL COMPANY
Farm - G.R. Smith No. 2

SEC. 21 T. 33 R. 12W
NW SW NW

Total Depth. 4950
Comm. 9-13-47 Comp. 10-8-47
Shot or Treated.
Contractor.
issued. 1-24-48

County. Barber
KANSAS



CASING			
13"	260'	cem.	250 sx.
8 5/8"	1754'	cem.	700 sx.
6"	4913'	cem.	500 sx.

Elevation. 1285 ft.

Production. Pot 2,243·B0 no wtr
Allowable 55 Bbl.

Figures Indicate Bottom of Formations.

red bed	100
shale & shells	260
red bed & shale	500
shale	735
shale & shells	1300
salt	1410
shale & shells	1705
lime	1785
lime & shale	1935
shale & shells	2110
lime	2520
lime & shale	2645
shale	3100
lime & shale	3355
lime	3645
sand & shale	3770
lime & shale	3950
lime	4400
lime & shale	4470
lime	4610
lime & shale	4659
lime	4685
lime & shale	4742
shale	4795
lime	4820
lime & chert	4895
shale & lime	4905
shale	4915
Coring	4925
sand	4950
Total Depth.	

TOPS:

Lansing	3920
Mississippi	4522
Viola	4795
Simpson	4894