

30-33-12W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. TRANS ERA PETROLEUM, INC.
Farm. McCullough No. 1


SEC. 30 T. 33 R. 12W
NW NW NE

Total Depth. 5070
Comm. 4-30-55
Shot or Treated.
Contractor.
Issued. 8-6-55

Comp. 5-29-55

County Barber

KANSAS



8 5/8 @ CASING: 305' w/ 200 sx cmt.
5 1/2 @ 4574' w/ 100 sx cmt.

Elevation. 1503

Production. 1,600,000 CFG

Figures indicate Bottom of Formations.

sand & red bed	35
sand	50
red bed, shale & shells	235
shale & red rock	825
shale & shells	1450
shale & lime	3675
shale	3730
lime & shale	3908
lime	4146
lime & chert	4200
lime	4211
shale & lime	4220
lime	4327
shale & lime	4703
shale	4737
Viola	4795
lime & shale	4922
shale	4991
shale & sand	5033
Arbuckle	5070
Total Depth	

SCOUT TOPS:

Heebner	3740
Toronto	3762
Douglas	3784
Lansing	3874
Mississippi lime	4450
Kinderhook	4644
Viola	4784
Arbuckle	5026