

32-33-12W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


SKELLY OIL CO.

Company- Claude Wentworth Drilling Co. Inc.,
Farm- B. G. Smith No. 1

SEC. 32 T. 33 R.12W

C NE SW
660' from N L 660' from

County E L Barber KANSAS



Total Depth. 4715'
Comm. 8-21-57 Comp. 9-9-57
Shot or Treated.
Contractor. Claude Wentworth Drilling Co. Inc.,
Issued. 11-16-57

CASING:

8 5/8" @ 295' W/175 sks. cem.

Elevation. 1170' D. F.

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	325
Reamed 9" hole to 12 3/4" @ 295'	
shale & shells	1195
shale & lime	3250
lime & shale	3825
lime	4360
shale & lime	4453
lime	4534
White to buff, fine to coarsely crystalline limestone, trace of fractured and vuggy partly chalky, very slight porosity, no shows	4575
Limestone, partly chalky and partly shaly, no porosity or shows	4589
shale, light brown and red, no shows	4594
Limestone, as above, slightly cherty, no porosity or shows	4635
lime	4655
lime & shale	4715
Total Depth	4715'

Tops:

Heebner Shale	3698
Lansing Lime	3872
Marmaton	4422
Mississippi	4530
Kinderhook	4694

Drill Stem Tests: Ran Halliburton

- #1 packer set at 4937', used 38' anchor, open 1 hr. good blow of air for 10 mins. no rec. LFP-0 FVP-0, BHP-0 in 20 mins.
- #2 packer set at 4537' used 38' anchor, open 1 hr. very weak blow of air for 35 mins., rec. 20' of drilling mud, IFP-35#, FFP-22#. BHP-0# in 15 mins.

#3 packer set at 4575' used 60' anchor, open 1 hr. weak blow of air through out, rec. 40' drilling mud, IFP-55#, FFP-55# BHP-80#, 20 mins.

Ran Schlumberger Survey.