

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

API No. 15 — 007 — 20,379
County Number

S. 36 T. 33 R. 12 W
Loc. 660' FSL & 660' FEL

Operator
Sands Drilling Company

County Barber

Address
912 Philtower Building, Tulsa, Oklahoma 74103


Well No. #1 Lease Name Nurse Bevans

Footage Location
660' feet from (E) (S) line 660' feet from (E) (W) line

Principal Contractor DNB Drilling Geologist Bob Sandridge

Spud Date 1-13-76 Total Depth 4763' P.B.T.D.

Date Completed 1-23-76 Oil Purchaser



Elev.: Gr. _____

DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	28	207'	regular	170	3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Plugged as follows: 50 sk plug 257'-152'. 15 sk plug 45'-0'	
5' sk plug in rat hole & mouse hole.	

INITIAL PRODUCTION

Date of first production <u>dry hole</u>	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Sands Drilling Co.		DESIGNATE TYPE OF COMP.: C DRY HOLE, SWDV., ETC.: dry hole
Well No. 1	Lease Name Nurse Bevans	
S 36 T 33S R 12 W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4586-4642'				
Open 30 minutes				
SI 60 minutes				
Open 90 minutes				
SI 120 minutes				
4759' IH 2407				
IF 8-8				
ISI 16				
FF 8-8				
FSI 16				
FH 2391				
4576' IH 2528				
IF 34-34				
ISI 43				
FF 34-34				
FSI 4310				
FH 2510				
BHT 115°				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Manager Drilling & Production Title
	January 26, 1976 Date

State Geological Survey
WICHITA, BRANCH

DRILLERS' LOG

15-007-20379
36-33-12W

SANDS DRILLING COMPANY
No. 1 Nurse-Bevans
C SE SE, Sec. 36-33S-12W
Barber County, Kansas

Commenced: 1-13-76
Completed: 1-22-76

Surface Casing: 199' of
8-5/8" cemented w/170 sx
common cement, 2 1/2 cc.
1-14-76

FORMATION

DEPTH

Red Bed	0 - 180
Shale & Sand	180 - 800
Shale & Lime	800 - 2345
Lime & Shale	2345 - 2810
Shale & Lime	2810 - 3000
Lime & Shale	3000 - 3505
Shale & Lime	3505 - 3730
Lime & Shale	3730 - 3940
Lime	3940 - 4110
Lime & Shale	4110 - 4270
Lime	4270 - 4585
Cherty Lime	4585 - 4663
Lime	4663 - 4763 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 28th day of January, 1976.

Ella Priess
Ella Priess, Notary Public

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976