

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Building, Wichita, Kansas.

PLOTTED
 J. E. Jameson
 12-33-13W

BARBARA OIL COMPANY.
 Lytle No. 3.


SEC. 12 T. 33 R. 13W.
 Cen SE NE

Total Depth, 4699 P.B. 4572

JUL 27 1935

County, Barber

Comm. 4-4-35 Comp. 6-24-35
 Shot or Treated. 2000 gal acid. 4503-4568
 Contractor. Rose Spring Drilling Co.
 Issued. 7-27-35.



CASING.

15 1/2" 182' 8 1/4" 4535'

Elevation.

Production. ~~2 1/2 M. cu ft Gas~~
 1,500,000 GAS

Figures Indicate Bottom of Formations

red bed & shale	675	shale & little brkn sand	3879
gyp and shale	798	broken lime (Detrital)	3880
shale	1020	cored	
shale	1106	broken lime (Detrital)	3882
shale and shells	1470	slate blk	3898
shale and salt	1570	broken lime	3960
shale and shells	1715	lime	3980
lime broken	1845	broken lime	4003
lime	2037	lime	4022
broken lime	2095	broken lime	4058
shale	2105	lime	4095
broken lime	2130	shale	4105
lime	2159	broken lime	4129
broken lime	2200	shale	4136
lime	2225	lime	4142
shale	2235	shale & lime shells	4164
shale and shells	2256	lime	4170
broken lime	2260	shale	4190
lime	2372	lime	4200
broken lime	2438	shale	4225
lime	2464	lime	4240
broken lime	2530	shale	4263
shale & lime shells	2670	lime	4272
broken lime	2685	lime hard	4285
shale & lime shells	2720	shale	4303
lime	2740	broken lime	4320
broken lime	2767	lime	4360
shale & shells	2790	shale	4375
red rock	2799	broken lime	4395
shale & shells	2810	shale	4415
broken lime	2840	broken lime	4450
shale	2865	shale & lime shells	4480
lime	2869	cored at 4480-90	
shale	2885	lime hard (core)	4490
shale & shells	2893	shale dark green breaks	
lime	2918	lime	4498
broken lime	2968	shale	4505
shale Hard	2990	sand & green shale (oil)	4508 core
lime	3014	chat	4513
shale hard	3070	lime Porous (gas)	4517
lime	3075	lime Porous	4535
shale and shells	3107	corrected 4535 equals 4550	
lime	3153	CABLE LOG.	
broken lime	3189	4550-4699	
lime	3195	sdv lime	4572
shale & lime shells	3260	shale red	4577
sticky shale	3266	lime red shale breaks	4591
broken lime	3286	lime hard	4599
shale & shells	3320	lime broken	4609
broken lime	3405	lime soft	4622
lime	3457	lime hard	4634
broken lime	3467	broken lime (grey shale breaks)	4649
shale hard	3530	slate blue	4665
shale hard & lime	3566	shale blue lime shells	4680
shale	3795		
shale & lime shells	3811	lime and chat	4692
shale and hd slate shells	3860	lime hard	4699
		Total Depth. P.B. 4572	