

14-33-13W


BARBARA OIL & GAS CO.  
 Magnison No. 2.

SEC. 14 T. 33 R. 13W  
 Cen E/2 SW

Total Depth. 4827'  
 Comm. 11-12-38 Comp. 12-28-38  
 Shot or Treated.  
 Contractor. Springrose Drlg.Co.  
 Issued. 1-21-39

County. Barber

JAN 21 1939



CASING:  
 10 3/4" 280'  
 7" 4440'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay red & gyp shale	282	shale	4435
red rock	830	lime	4439
gyp & shells	850	Top Chat	4439
gyp & shale	1270	chatty lime	4440
shale, gyp & salt	1450	brkn chat	4448
shale, lime shells	1705	chatty lime	4458
gyp & shale	1725	shale	4467
anhydrite & shale	1785	sdv chat	4471
lime	1820	lime shells	4473
lime & shale	1840	chat	4479
lime & gyp	1895	brkn chat & shale	4490
shale & gyp	1945	brkn chat & green	
lime & shale	2090	shale	4498
lime	2125	brkn conglomerate	4521
sand	2140	red rock	4527
lime	2170	shale sticky	4532
shale & lime	2295	lime & chert	4550
lime	2315	brkn lime & chert	4557
shale & lime	2410	brkn lime	4580
shale sticky	2445	lime & chert	4598
shale & lime	2810	shale	4625
shale sticky	2820	lime shells & shale	4637
lime shells & shale	2845	lime brown	4665
lime & shale	3010	brkn lime & shale	4680
lime brkn	3040	lime	4700
lime	3395	shale	4737
shale	3425	lime shells	4741
shale sticky	3445	shale blk	4766
shale & lime	3460	lime shells	4769
shale sticky	3615	shale blk	4785
sand & shale	3710	brkn lime	4795
shale	3755	brkn lime sdv	4816
sand & shale	3805	Top Viola	4816
sand	3875	lime	4827
sand & shale	3905	Total Depth.	
Top Kansas City	3905		
lime & shale	3932		
lime brkn	3960		
lime	4055		
lime brkn	4075		
lime sdv	4090		
lime	4130		
lime brkn	4165		
lime brkn sdv	4190		
lime	4205		
lime brkn sdv	4230		
lime & trace chat	4275		
lime brkn	4305		
lime	4323		
lime brkn & shale	4350		
Top Oswego	4350		
lime blk	4360		
lime brkn sdv	4370		
shale blk	4378		
lime brkn sdv	4385		
lime brkn sdv & chat	4390		
brkn chatty lime	4395		
lime & shale	4415		
brkn sdv lime	4425		