


BARBARA OIL CO.
B.E. Holmes No. 1-A

SEC. 15 T.33 R. 13W
C E/2 SE

DEEPENING RECORD

Total Depth. 4851'
Comm. 12-22-36 Comp. 3-3-37
Shot or Treated.
Contractor. Rose Spring Drlg. Co.
Issued. 5-21-38

County. Barber



CASING:

12 1/2" 314'
7" 4505'

Elevation.

Production. Pot. 441 B.O.

Figures Indicate Bottom of Formations. 11,000,000 cu ft gas.

red rock & gypsum	270	sdv lime	3190	shale	4484
red rock	340	brkn lime	3220	shale & lime	4490
red rock, shale & gypsum shells	555	sdv lime	3240	sdv lime	4495
shale & gypsum shells	1145	lime	3270	brkn lime	4515
shale & salt	1250	shale sticky	3290	brkn lime & shale green	4520
shale & lime shells	1360	shale & lime shells	3305	lime	4538
salt, shale & lime shells	1525	shale	3315	chat	4548
shale & lime	1585	sdv lime	3330	lime	4560
lime	1610	shale & lime	3360	lime & chat	4567
shale & gypsum	1750	lime	3375	chert & lime	4581
gypsum	1770	sdv lime	3385	lime	4600
gypsum & brkn lime	1790	lime	3410	brkn lime	4628
lime & gypsum	1925	shale	3433	shale	4635
lime	1929	sand	3437	red rock, shale & lime shells	4645
shale & lime	1929	sand hrd	3441	slate shells	4655
lime	2000	shale	3448	red rock	4663
shale & lime	2010	sticky shale	3560	shale	4690
shale	2015	shale & lime shells	3570	slate blue	4698
shale & lime	2055	shale	3595	lime	4720
shale	2065	shale & lime shells	3635	brkn lime	4732
sticky shale	2080	shale	3770	lime	4738
lime	2095	shale & lime shells	3825	lime hrd	4740
sticky shale	2120	sand hrd & shale	3845	shale white	4765
lime & shale	2145	lime & shale	3855	lime	4768
sticky shale	2175	shale	3873	shale black	4772
sdv lime hrd	2210	sticky shale	3880	shale blue	4795
sdv shale & lime	2225	shale	3903	lime	4802
sdv lime hrd	2270	brkn lime	3915	shale black	4845
lime & shale	2290	sdv shale	3930	Viola lime	4847
shale & lime shells	2380	sand	3965	Total Depth.	
shale & lime	2450	sdv shale	3976		
shale	2490	coring	3995		
brkn lime	2510	lime	4025		
shale	2530	brkn lime	4085		
sdv shale & lime	2540	lime	4150		
brkn lime	2560	sdv lime	4175		
shale & lime	2580	lime	4190		
brkn lime	2620	sdv lime	4205		
shale & lime	2665	lime hrd	4220		
sticky shale	2680	sdv lime	4225		
sdv lime	2690	sand hrd	4228		
lime hrd	2710	lime	4233		
lime	2715	lime sdv hrd	4258		
shale & lime	2730	brkn lime	4263		
sticky shale	2740	sdv lime	4285		
brkn lime	2758	lime	4295		
shale & lime	2835	sticky shale	4304		
shale	2875	brkn lime	4324		
shale & sdv lime	2920	shale & lime	4338		
shale & lime	2955	shale	4355		
brkn lime	2980	shale & lime	4360		
sdv shale & lime	3030	brkn lime	4395		
brkn lime	3050	sdv lime hrd	4409		
lime	3105	sdv lime & shale	4416		
sticky shale & lime	3124	shale	4418		
shale	3140	brkn lime	4434		
brkn lime	3150	lime	4465		
	3170	brkn lime	4475		

DEEPENING RECORD

Comm. 7-17-37 Comp. 8-4-37
Production. Pot. 441 B.
Old T.D. 4847'

Viola Lime 4847-51

Total Depth.