


BARBARA OIL CO.
Root No. 3-B

SEC. 15 T. 33 R. 13W.
CSL NE $\frac{1}{4}$

Total Depth. 4900
Comm. 7-14-39 Comp. 8-25-39
Shot or Treated.
Contractor. Springrose Drlg. Co.
Issued. 10-21-39

County Barber.



CASING.

10" 266'
7" 4805'

Elevation.

Production. 25,000,000 G.

Figures Indicate Bottom of Formations.

red rock and gyp	266
red rock	725
shale and shells	1000
red shale and shells	1125
shale grey & gyp	1190
gyp, shells & shale	1405
salt and shale	1600
shale and gyp	1750
lime shells & shale	1815
shale and lime	1830
shale & gyp	1955
shale and lime	2020
lime	2035
shale and lime	2100
sticky shale	2120
brkn lime	2145
lime and shale	2250
shale	2280
lime	2315
shale and lime	2420
sticky shale	2450
broken lime	2530
shale	2575
lime	2600
lime and shale	2685
sticky shale & lime	2710
broken lime	2790
lime and shale	2910
lime sticky shab	2955
brkn lime	2985
sticky shale	3065
lime and shale	3145
sticky shale & lime	3165
lime	3270
broken lime	3335
lime	3418
brkn sdy lime	3425
lime	3455
lime & sticky shale	3480
sticky shale	3575
lime shells & shale	3700
sand	3720
lime	3735
sticky shale	3755
shale	3845
shale and lime	3890
sdly shale	3950
shale	3975
broken lime	4000
K.C. lime	4045
lime	4090
lime hard	4110
lime	4160
brkn lime	4180
lime hard brown	4198
lime	4325
lime and shale	4345

lime	4360
lime shells & shale	4400
lime blk	4410
lime and shale	4445
chatty lime	4455
sdly lime	4475
broken lime	4485
shale	4490
broken lime	4508
shale	4512
brkn chort & lime	4520
brkn chatty lime	4540
shale	4548
chort	4555
chort and brown sand	4579
shale	4590
shale and lime	4630
shale	4655
lime and shale	4715
sdly lime hard	4730
lime hard	4736
lime and shale	4780
shale blue	4790
shale	4805
lime & shale	4820
shale blk	4860
lime	4881
small sh gas	4879-4881
lime	4900

Total Depth.

Casing perforated 4549-4579 and
completed for 25 Million Cu ft Gas.