

18-33-13W

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY BARBARA OIL

SEC. 18 T. 33 R. 13W  
 LOC. C NW NW

FARM Storm NO. 1

TOTAL DEPTH 5202'  
 COMM. 8-24-67 COMP. 9-11-67  
 SHOT OR TREATED  
 CONTRACTOR Gabbert-Jones  
 ISSUED 11-4-67

COUNTY Barber



CASING

20	10	
15	8 5/8" 223'	cem w/ 200 SX
12	6	
13	5	

ELEVATION 1873' KB

PRODUCTION DRY/SIMP

FIGURES INDICATE BOTTOM OF FORMATIONS

PTH	FORMATION	REMARKS
FROM 0	SURFACE CLAY	
To 40	RED BED	
223	RED BED	
315	RED BED AND SAND	
400	RED ROCK AND GYP SHELLS	
1065	SHALE AND SHELLS	
1770	LIME AND SHALE	
2090	LIME	
2655	LIME AND SHALE	
4210	LIME	
4713	LIME AND CHERT	
4735	LIME	
4975	LIME AND SHALE	
5008	LIME	
5145	LIME AND SAND	
5164	LIME AND SANDY SHALE	
5200	LIME	
5205		
TO 05		

DRY AND ABANDONED

RAN 6 JOINTS 8 5/8" CASING, SET @ 223' w/200 BAGGS CEMENT.

TOPS: LOG

Elgin Zone	3830
Heebner	3988
Toronto	4012
Douglas shale	4044
1st sand	4082
Brown lime	4192
Lansing	4200
Base Kansas City	4590
Marmaton-Massy	4664
Mississippi Chat	4716
Kinderhook	4950
Maquoketa	4983
Viola	5025
Simpson shale	5150
Simpson sand	5170