

BARBARA OIL CO.
Mark No. 1.

SEC. 19 T. 53 R. 13 W
Cen NE₁

Total Depth. 5085'
Comm. 4-23-43 Comp. 6-8-43
Shot or Treated.
Contractor. S.A. Springer
Issued. 7-10-43

County. Barber



CASING:

7" 4787'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil-sand	0-60	shale gy	4829
sdv clay	180	lime brkn	4839
red rock	260	lime sdv	4873
red rock-shale gy	300	shale blk	4949
shale-red rock	1000	lime	5039
shale	1100	lime brkn	5056
shale-lime	1640	lime wh	5062
salt-shale	1730	shale green	5072
shale-gyp	1820	sand	5075
lime	1885	shale blue	5085
lime-anhydrite	1975	Total Depth.	
anhydrite	2085		
lime-shale	2155		
shale	2180	Gun perf. 4722-69	
lime-shale	2225	Dry hole-no sh oil, gas	
sdv lime-shale	2270	or wtr	
shale-lime	2315		
lime brkn	2460		
lime	2490		
lime-shale	3010		
lime	3035		
shale	3070		
lime-shale	3140		
shale	3220		
limo	3540		
shale sticky	3565		
shale	3820		
lime sdv	3870		
shale sdv	3885		
shale	3920		
lime-shale	4000		
shale	4015		
lime brkn	4040		
slate blk	4075		
shale sticky	4098		
lime brkn	4150		
lime	4425		
lime brkn	4460		
lime brown hd	4472		
slate blk	4494		
lime hd	4505		
shale-lime	4510		
lime blk	4520		
lime brkn	4530		
shale-lime shells	4675		
lime wh cherty	4692		
lime cherty	4714		
shale	4718		
lime-chert-chat	4732		
lime cherty sdv	4748		
lime sdv & chert	4769		
shale gy	4787		
Cable tool log:			
lime brkn-shale	4800		
shale green	4809		
lime	4824		