

24-33-13N
R. S.
DEC 22 1930

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG WICHITA KANSAS.

Location Cen SW NW. Sec. 24 T.33 R.13W
County- Barber. No. 1

Casing Record Farm- Hamblin
20" 8 1/4" 4400 Company- The Barbara Oil Co.
15 1/2" 143 65/8" Contr.-
12 3/4" 53/16" 4440 Comm.- 5/18/30 Comp.- 9/23/30
Total Depth 4528' Shot Quarts Between
Corr spondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations. Initial Production
Date Issued. 12/20/1930'. Est. 19 M. Gas.

Formation	Depth	Formation	Depth
red rock & gyp		lime	4112
shells	540	shale	4124
shale & shells	843	sand lime hrd	4154
slate & shells	1473	brkn lime	4180
sdv lime	1503	lime hrd	4228
shale	1518	shale	4237
sdv lime	1593	lime	4247
red rock	1602	shale	4248
lime	1790	lime	4260
shale	1793	sand	4262
lime	1982	sdv lime	4287
shale	2012	shale	4297
lime	2052	lime	4320
black lime & shale	2259	shale	4325
water sand	2268	lime	4336
lime black	2364	shale	4350
lime black & shale	2423	lime hrd	4354
water sand	2434	lime brkn	4400
lime & shale breaks	2581	Rotary hole finished	
B. lime	2623	at 4400'	
shale	2635	STANDARD TOOL RECORD	
slate & shells	2838	lime	4425
gumbo & gyp	2917	lime brkn	4445
chalky gyp	2940	lime hrd	4487
slate & shells	3018	1st gas 4487	
lime	3026	Through gas at 4511	
shale & shells	3076	lime brown	4528
brkn lime	3167	Total Depth	4528
shale	3197		
lime	3207	First gas at 4487'--200,000' of Gas	
gumbo	3222	Second gas at 4494 1 1/2 Mil	
lime & shale	3280	Third gas at 4498 2 3/4 Mil.	
brkn lime	3350	Fourth Gas at 4500 3 Mil	
sticky shale & gyp	3375	Fifth gas at 4501 4 Mil	
B. lime	3386	10 Mil 4502'	
gyp shale	3446	15Mil Gas 4503	
shale & gyp	3495	20 Mil Gas 4506	
B. lime	3505	More gas 4508'.	
shale	3517	Through sand at 4511	
lime & gyp	3622	Bottom of hole 4528	
lime	3721		
~~sticky shale~~	3771		
B. shale	3824		
lime	3838		
sand	3850		
sdv lime	3871		
sticky shale	3892		
B. shale & brkn lime	3957		
lime white	4050		
brkn lime	4075		
shale	4080		
brkn lime	4104		
shale	4107		