

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas


25-33-13W

Company- PETROLEUM, INC.
Farm- Page-Holmes No. Unit 1

SEC. 25 T. 33 R. 13W
SE SE SE

Total Depth. 4632'
Comm. 7-17-56 Comp. 8-2-56
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 12-6-58

County Barber
KANSAS



Elevation. 1530' DF

Production. 4,840,000 CFG

CASING:

8 5/8" 301' w/225 sx cem.
5 1/2" 4626' w/100 sx cem.

Figures Indicate Bottom of Formations.

sand, shale, red bed	303
red bed, shale	890
shale, shells	1800
shale, lime	2630
shale, shells	2845
shale, lime	3005
shells	3080
lime, shale	4040
lime	4323
shale, lime	4520
lime	4620 RTD
lime	4632
Total Depth	

TOPS:	SAMPLE SCHL.	
Elgin	3568	3568
Heebner	3730=	3742
Douglas Sand	3765	3763
Lansing	3917	3926
B/Kansas City	4390	4398
Mississippi Chert	4520	4530
Mississippi Lime	4571	4582

DST #1, 3933-4040, Open 1 hr., strong blow throughout, red. 2520' muddy salt wtr., IFP 500%, FFP 1300%, BHP 1550#/30 mins.

DST #2, 4516-59, Open 1 hr., gas to surface in 3 mins., gauged 500 MCFGD/15 mins., rec. 50' GCM, IFP 200%, FFP 200%, BHP 1850#/30 mins.

DST #3, 4559-4620, Open 1 hr., good blow throughout, rec. 330' mud, no pressures recorded.