

State Geological Survey
WICHITA BRANCH

DRILLERS LOG

No. 2 Falen-Holmes

15-007-20473
33-33.13W

CASING RECORD:

COMPANY: Patton Oil Company

DESCRIPTION:

8 5/8" @ 434'
w/350 sx cmt.

CONTRACTOR: Red Tiger Drilling Company

100' E of C SW/4 SE/4
Sec. 33-T33S-R13W
Barber County, Kansas

COMMENCED: February 23, 1977

COMPLETED: March 12, 1977

TOTAL DEPTH: 5,310'

ELEVATION: 1,709' KB

FORMATION	FROM	TO	REMARKS
Surface hole	0	440	
Sand & Shale	440	1370	
Shale	1370	1885	
Shale & Lime	1885	2137	
Lime	2137	2875	
Lime & Shale	2875	3165	
Lime	3165	5310	
RTD		5310	

PATTON OIL CO.
5660 SO. SYRACUSE CIRCLE #2 FALEN-HOLMES 33-33-13W
ENGLEWOOD, CO. 100'E, C SW SE
CONTR RED TIGER DRG. CO. CTV BARBER
GEOL STEVE KRIEDLER FIELD WC (3/4 S OF MEDICINE LODGE-
BOGGS)
E 1709 KB CM 2/23/77 CARD ISSUED 3/17/77 D&A/SIMP

API 15-007-20,473

SMP	TOPS	DEPTH	DATUM
COTTONWD	2706	- 997	
TARK	3208	-1499	
OP	3432	-1723	
IEEB	3966	-2257	
DOUG SD	3982	-2273	
2ND DOUG SD	4022	-2313	
RR LM	4142	-2433	
LKC	4150	-2441	
KIND SH	4946	-3237	
CHATT	4997	-3288	
VIOLA	5043	-3334	
SIMP SH	5163	-3454	
SIMP SD	5168	-3459	
RTD	5263	-3554	

8-5/8" 434/350sx
NO LOG
DST (1) 3572-3602/30-30-30-30, 4'DM,
SIP 46-46# FP 46-46#
DST (2) 3942-4010/60-30-30-30, 1200'
GIP, 120'DM, SIP 144-368# FP 69-
69#
DST (3) 4655-4705/30-30-30-30, 15'DM,
SIP 65-43# FP 43-43#
DST (4) 5125-5175/30-30-30-30, 530'
SG&OCM, 670'SGCSW, SIP 2361-
2319# FP 272-674#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS