

WC

4

Field

State Kansas

County Meade

Company Shamrock Oil & Gas

Farm North

Well No. 1

Sec. 13

Twp. Blk. 33S

Range Survey 30W

fr N

fr E

fr S

fr W

of NE SW

Contractor Cree Drlg.

*Duff DHM*

Remarks Morr Test (Col. & U.P. FO)

Comm. 7-31-55

Comp. 9-21-55

Elev. 2718

T. D. 5845

P. B.

Pay

I. P. D+A

R. P.

Casing Record: 13 3/8 638/500

7

20 10 3/4

5 1/2

16 8 5/8 2731/800

*Sample by Co*

		Tops
8-3-55	Ø 900.	Dolo 2729
		Lansy 4573
AUG 10 1955	Ø 2853	Morr 5214
AUG 17 1955	<u>stick drill pipe @ 4226</u>	<u>atah 5390</u>
	<u>&amp; fishing</u>	<u>atah 5506</u>
AUG 24 1955	<u>rec pipe</u>	<u>Morr 5721</u>
	<u>Ø 4908</u>	<u>Misc 5800</u>
AUG 31 1955	<u>#1 5739-62</u>	<u>rec 7'</u>
	<u>7' SA, w/2 stringer lms.</u>	

~~#2 5761-90 rec 22' sh & lms, n.s.~~  
~~#3 5790-5833~~

SEP 7 1955  
 Ø #2 5761-90  
 5 7/8" bl + gr potu sh. sh.  
 5" lite glw lms. trace fore  
 1 1/2" spy sh.  
 1' 10" lms as above  
 1' lite spy to grw sh  
 2" lms as above  
 2' 5" shi edy glw shale.

- 1'3" fm to crs. glu. crinoidal tite lmn.
- 6" lite gray to gen sh.
- 1'2" lmn as above.
- 6" lmn as " " w vert frag.
- 5" sdy lmn + lmy sd. scat. stain tite
- 1.7" gen sli glu. sh.
- 1" gray to gen sh. w thin lamination of tite glu. sd.
- 8" brow dens. lmn w embedded fm to crs. sd streaks
- 5'2" gray to gen rotten sh

# 5790-5833 sec 43'

- 1' sh w streak tite crins lmn
- 1'5" sh.
- 1'5" tite crinoidal lmn
- 3" rotten sh.
- 1' interbedded tite lmn + sh
- 3" sh.
- 4'6" tite crinoidal lmn. frag from 5792-98
- 3" sh. w archomedes
- 3' tite lmn. stringy sh.
- 1' sh. trace lmn.
- 5" sh
- 5" tite lmn
- 2" sh.
- 6" tite lmn + sh.
- 1'6" tite lmn. w frag bleed oil along frag planes
- 2' tite lmn
- 1'9" tite lmn + sh.
- 2" bushy marl
- 1" sh.
- 4'6" buff to lmn fm to crs. tite crin. lmn
- 6" sh.
- 1' tite crins lmn.
- 9' dk gray sh.
- 2' tite lmn
- 1' lmn + sh.

Field \_\_\_\_\_  
 State \_\_\_\_\_ County \_\_\_\_\_  
 Company \_\_\_\_\_  
 Farm \_\_\_\_\_ Well No. \_\_\_\_\_  
 Sec. \_\_\_\_\_ Twp. Blk. \_\_\_\_\_ Range Survey \_\_\_\_\_  
 \_\_\_\_\_ fr N \_\_\_\_\_ fr E \_\_\_\_\_ fr S \_\_\_\_\_ fr W \_\_\_\_\_  
 of \_\_\_\_\_  
 Contractor \_\_\_\_\_  
 Remarks \_\_\_\_\_  
 Comm. \_\_\_\_\_ Comp. \_\_\_\_\_  
 Elev. \_\_\_\_\_ T. D. \_\_\_\_\_ P. B. \_\_\_\_\_  
 Pay \_\_\_\_\_

*North*

I. P. \_\_\_\_\_ R. P. \_\_\_\_\_  
 Casing Record: 13 3/8 \_\_\_\_\_ 7 \_\_\_\_\_  
 20 \_\_\_\_\_ 10 3/4 \_\_\_\_\_ 5 1/2 \_\_\_\_\_  
 16 \_\_\_\_\_ 8 5/8 \_\_\_\_\_

5833-45pc 9'6" T6ps  
 9.6 fm to the N side lmn. w streaks  
 out stain flow. of odor sent  
 you sh. spots.  
 DST 5833 1/2 - 45 open 2 1/2 hrs  
 wk blv. inv to good in 25 min  
 rec 540' g in DP 30' M shi  
 run of oil FP 0 BH 125/30  
 HH 3040  
 RTD 5845  
 Aln 5845

D+A

misc

SEP 1 1955

SEP 2 1 1955

Log tops by Co

Her	2710
Kri	2770
Winf	2819
V FC Bil	2876
L " "	2952
Florene	2996
C.G.	3179
Fang	4606
Mdm	5231
Cik	5400
at	5511
Mor	5738
Chest	5805

⌀