

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


2-33-14W

Company- HONAKER-DAVIS DRLG. ET AL
Farm- Ott No. 1

SEC. 2 T. 33 R. 14W
SW NW NE

Total Depth. 4800'
Comm. 6-20-57 Comp. 7-6-57
Shot or Treated.
Contractor. Honaker-Davis Drlg.
Issued. 9-21-57

County Barber
KANSAS



CASING:
8 5/8" 283' cem w/250 sx.

Elevation. 1956' RB

Production. Dry

Figures indicate Bottom of Formations.

surface soil	15
sand	60
red bed & shale	745
shale & shells	2115
shale & lime	2275
lime & shale	2473
lime	2590
lime & shale	2690
shale & lime	3065
shale	3460
shale & shells	3565
lime & shale	3910
shale & lime	3985
lime & shale	4245
lime	4769
chert	4775
lime	4800 RTD
Total Depth	

TOPS:

Elgin Sand	3995
Heebner	4054
Douglas Sand	4207
Lansing-Kansas City	4236
Mississippian Chert	4766

DRILL STEM TESTS (HALLIBURTON)

#1 4588-4628', tool open 20, 60, and 20 mins.
weak blow throughout. rec. 150' muddy water
IBHP 1680#, FBHP 1550#, IFP 50#, FFP 50#.

#2 4698-4724', tool open 20" - 20" - 20"
weak blow for 2 min. (flushed tool twice)
Rec. 25' mud BHP 30#.

#3 4766-4775', tool open 20" - 60" - 20"
fair blow thruout, rec. 25' mud, IBHP 990#,
FBHP 70#, IFP 17#, FFP 35#.

#4 4775-4784', tool open 20" - 60" - 20"
weak blow (flushed tool twice) rec. 73'
mud, IBHP 480#, FBHP 70#.