

IMPORTANT  
Kans. Geo. Survey request  
samples on this well.

15-007-20557

API No. 15 — 007 — 20,557  
County Number

S. 5 T. 33 R. 14 <sup>K</sup>/<sub>W</sub>  
Loc. 2310' FSL & 660' FEL  
County Barber

Operator  
Texas Oil & Gas Corp.

Address  
Suite 300-200 West Douglas Wichita, Kansas 67202


Well No. #1 Lease Name Cline-Mills

Footage Location  
2310 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor H-30 Drlg., Inc. Geologist High Plains Consulting Ltd.

Spud Date 11-7-77 Total Depth 4750' P.B.T.D. N/A

Date Completed 11-17-77 Oil Purchaser N/A



Elev.: Gr. 1771'  
DF 1776' KB 1778'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	394'	Common	375	2% Gel, 3% CaCl

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
<b>TUBING RECORD</b>			N/A	N/A	N/A
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
N/A	N/A

**INITIAL PRODUCTION**

Date of first production N/A	Producing method (flowing, pumping, gas lift, etc.) N/A
RATE OF PRODUCTION PER 24 HOURS	Oil <u>N/A</u> bbls. Gas <u>N/A</u> MCF Water <u>N/A</u> bbls. Gas-oil ratio <u>N/A</u> CFPB
Disposition of gas (vented, used on lease or sold) N/A	Producing interval (s) N/A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

perator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Texas Oil & Gas Corp.

Well No. 1	Lease Name Cline-Mills	Dry Hole
---------------	---------------------------	----------

S 5 T 33S R 14 <sup>F</sup> <sub>W</sub>

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2128	-350		
Winfield	2222	-444		
Towanda	2285	-507		
Florence	2388	-610		
Wreford	2493	-715		
Foraker	2850	-1072		
Onaga	2986	-1208		
Wabaunsee	3027	-1249		
Stotler	3169	-1391		
Tarkio	3218	-1440		
Topeka	3432	-1654		
Lecompton	3752	-1974		
Heebner	3917	-2139		
Lower Douglas	4088	-2310		
Lansing	4110	-2332		
Kansas City	4190	-2412		
Swope	4454	-2676		
Hertha	4490	-2712		
Lenapah	4543	-2765		
Mississippi	4676	-2898		
TD	4750	-2972		
DST #1, 4647-95', (Mississippi) w/results as follows: IFP/30": 80-120#, GTS/5", 59 MCFD decr to 44 MCFD; ISIP/60": 1524#; FFP/45": 120-160#, 80 MCFD; FSIP/90": 1504#; Rec 40 GCM, 240' GCMW & 240' wtr.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Harold A. Brown</i>
	HAROLD A. BROWN District Geologist
	Signature
	Title
	November 18, 1977
	Date

COMPANY **Texas Oil and Gas Corp.**

SEC. **5** T. **33S** R. **14W**  
LOC. **2310' PSL & 600' PEL**

FARM **Cline-Mills** NO. **1**

TOTAL DEPTH **4,750'**

COUNTY **Barber**


COMM. **November 7, 1977**

COMP. **November 17, 1977**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED **November 25, 1977**



CASING

20	10	
15	8	-5/8" 394' cemented w/375 sxs cement ELEVATION 1,779' K.B.
12	6	
13	5	

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

<b>Red Bed and Shale</b>	<b>425'</b>
<b>Shale</b>	<b>2,112'</b>
<b>Lime and hale</b>	<b>2,240'</b>
<b>Shale and Lime</b>	<b>2,420'</b>
<b>Chert and Shale</b>	<b>2,640'</b>
<b>Shale and Lime</b>	<b>3,075'</b>
<b>Lime and Shale</b>	<b>4,395'</b>
<b>Shale and Lime</b>	<b>4,510'</b>
<b>Lime</b>	<b>4,625'</b>
<b>Lime and Chert</b>	<b>4,750'</b>
<b>Rotary Total Depth</b>	<b>4,750'</b>

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
\_\_\_\_\_  
Dean Britting

State of Kansas }  
County of Sedgwick } ss: