

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LION OIL CO.
 Farm- Anna

No. 1

SEC. 23 T. 33 R. 14W
 SW NE SE

Total Depth. 4965

Comm. 10-2-55


Comp. 10-17-55

Shot or Treated.

Contractor. Graham-Messman-Rinehart Drilling Co.

Issued. 1-14-56

County Barber
 KANSAS



CASING:

8 5/8 @ 273' w/ 175 sx cmt.
 5 1/2 @ 4965' w/ 225 sx cmt.

Elevation. 1897 DF

Production. 6,150,000 CFGPD

Figures indicate Bottom of Formations.

sand	57
red bed & sand	1090
red bed, sand & shale	1627
lime & shale	3960
lime, shale & sand	4080
shale & sand	4168
shale & lime	4285
lime	4384
lime & shale	4447
lime	4810
shale & chert	4825
lime	4840
lime & chert	4907
lime	4965
Total Depth	

TOPS:	SAMPLE	SCHLUM
Lecompton	3869	
Kanwoka	3900	3900
Elgin sand	3979	3979
Heebner	4077	4081
Douglas zone	4117	4118
Lansing	4266	4268
Mississippian	4814	4813
Schlumberger TD		4966

DST #4: 4825-40, open 1 hr. rec. 10'
 GCM, IFP O#, FFP 175#, BHP 285#/25 min.

DST #5: 4840-90, open 1 hr. rec. 30'
 SGCM, FP O#, BHP 320#/20 min.

DST #6: 4890-4907, open 1 hr. rec.
 40' SGCM, FP O#, BHP 1030#/20 min.

DST #1: 4115-63, open 1 hr. rec.
 310' SW, IFP 80#, FFP 200#, BHP 1310#/
 20 min.

DST #2: 4729-50, open 30 min. rec.
 30' VSOCM, BHP O#

DST #3: 4816-25, open 1 hr. gas to
 surf 4 min. 10 min gauge 98 MCF, 20
 min gauge 142 MCF, 30 min gauge 146 MCF
 45 min gauge 142 MCF, 55 min gauge
 138 MCF, rec. 35' SGCM, IFP & FFP 30#,
 BHP 1615#/30 min.