

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- GRAEHART-MILLER OIL COMPANY
Farm- Lenkner "A" **No.** 1

SEC. 24 **T.** 33 **R.** 11W
 C SE/4

Total Depth. 4909
Comm. 11-18-54 **Comp.** 12-4-54

County Barber
KANSAS

Shot or Treated.
Contractor. Graham-Messman-Rinehart Drlg. Co.
Issued. 3-19-55



CASING:

Elevation. 1840 KB

8 5/8" 280' com. w/200 sx
 5 1/2" 4852' com. w/75 sx

Production. 100 bbls. oil

Figures Indicate Bottom of Formations.

sand & clay	30
sandy redbed	106
redbed	280
sand & redbed	428
redbed & shale	1352
shale & lime	1645
lime & shale	3833
sandy lime & shale	3950
lime & shale	4446
lime	4519
lime & shale	4683
lime	4717
chert	4764
chert, lime & shale	4788
lime	4842
lime & shale	4909
Total depth	

Schlumberger Tops:

Heebner	4000
Douglas	4039
Lansing	4181
Mississippi	4719

Sample Tops:

Heebner	3998
Lansing	4178
Mississippi	4714