

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company. MAGNOLIA PETROLEUM CO.
Farm- William A. Wheat No. 3

SEC. 33 T. 33 R. 14W
C NW NE

Total Depth. 5191'
Comm. 11-1-58 Comp. 12-2-58
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 4-11-59

County Barber

KANSAS



CASING:
8 5/8" 385' cem w/275 sx.
5 1/2" 4760' cem w/200 sx.

Elevation. 1657' KB?
1707'

Production. 12,700,000 CFGPD

Figures Indicate Bottom of Formations.

surface soil & sand	590
shale & shells	2155
shale & lime	3175
shale & shells	3630
lime & shale	3720
shale	3876
lime	4585
lime & shale	4630
lime & chat	4685
lime	4694
lime & chat	4730
lime	4860
lime & shale	5035
lime & chat	5130
shale & lime	5191
Total Depth	

TOPS:	
Heebner	3880
Lansing-Kansas City	4069
Mississippian	4635
Kinderhook	4811
Chattanooga	4930
Viola	4980
Simpson	5112

DST #1 4640-94, packer failed

DST #2 4938-5021', op 1 hr., fr bl. rec.
10' DM, FP 25-35#, IBHP 340#/20 mins,
FBHP 680#/1 hr.

PERFORATIONS:
Perf. 4647-82 w/140 sh. acidized w/500 GMCA.
MP 1400#, min. & final 1100#, rate 2 BPM.