


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- William A. Wheat No. 4

SEC. 33 T. 33 R. 14W
C NW SE

Total Depth. 4830'
Comm. 6-5-59 Comp. 7-1-59
Shot or Treated.
Contractor. Peel Brothers
Issued. 10-10-59

County Barber
KANSAS



Elevation. 1621'

Production. 8,300,000 CFGPD

CASING:

8 5/8" 364' cem w/275 sx.
5 1/2" 4746' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface soil	40
shale & sand streaks	200
red bed	745
shale & shells	1785
shale & lime	2120
lime	2210
lime & shale	3270
lime	3340
shale & lime	3940
lime	4590
lime & shale	4635
lime	4814
lime & shale	4830
Total Depth	

TOPS:

Heebner	3860
Lansing	4049
Mississippi	4617
Kinderhook	4795

DST 4620-72', op 1 hr., SI 30 mins.
gas in 13 min. ga. 69,000 CFG/30 mins.
60,000 CFG/1 hr, IBHP 1830#, FBHP 1775#,
FP 15#, rec. 20' mud.

Perfs:

#1 4632-36 with 16 jets
#2 4642-4648 with /24 jets
#3 4656-4686 w/120 jets