

8-33-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SUNRAY DX OIL CO.  
Farm- Hazel Lendon No. 1

SEC. 8 T. 33 R. 15W  
C NE SW

Total Depth. 5095'  
Comm. 12-14-62 Comp. 1-4-63  
Shot or Treated.  
Contractor. Stickle Drilling Company  
Issued. 6-22-63

County Barber  
KANSAS



Elevation. 1784' BB

Production. 2,600,000 CFGPD/Viola  
3,400,000 CFGPD/  
Simpson Sand

CASING:

8" 1128' cem w/300 sx.  
5" 5094' cem w/150 sx.

Figures Indicate Bottom of Formations.

red bed & shale	190
red bed & shells w/Anhydrite stringers	770
shale & shells	2120
shale & lime	2285
lime	2425
lime & shale	2845
shale & lime	3050
shale	3280
shale & chalky lime	3486
lime & shale	3605
shale & lime	3890
lime & shale	4040
lime	4710
cherty lime	4745
lime	4865
sand	4880
lime & sand	4890
sand	4900
shale & lime	4924
sand & shale	4943
lime	5065
lime & chert	5095
Total Depth	

TOPS: LOG

Heebner	3917
Douglas	3996
Lansing	4064
Base Kansas City	4533
Marmaton	4542
Osage	4642
Kinderhook	4659
Viola	4693
Simpson	4827
Simpson Sand	4857
Arbuckle	4938