

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

State Geological Survey

S. 21 T. 33S R. 15 W

Loc. NW, SE

County Barber

API No. 15 — 007 — 21,138 WICHITA BRANCH
County Number

Operator

Petrosil Exploration Inc.

Address

2100 Two Oaks Plaza, 6730 LBJ Frwy., Dallas, Tex. 75240

Well No.

1

Lease Name

Beck

Footage Location

660

feet from (N) line

560

feet from (W) line

Principal Contractor

The Ramco Drilling Corp.

Geologist

Jim Sewell

Spud Date

5-19-81

Date Completed

6-11-81

Total Depth

5514'

P.B.T.D.


4790'

Directional Deviation

-

Oil and/or Gas Purchaser

Negotiating Contract

640 Acres
N

Locate well correctly

Elev.: Gr. 1801

DF 1821 KB 1822

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13-3/4"	10-3/4"	45#	272'	Regular	200	3% CaCl, 2% Gel
Production	7-7/8"	4 1/2"	10.5#	4840'	Pozmix	175	7 1/2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
-	-	-	2	3-1/8" Gun	4732'-4740'
					4687'-4694'

TUBING RECORD

Size	Setting depth	Packer set at			
2-3/8"	4680'	4680'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2,000 Gals. 15% Hcl Acid	4732'-4694'

INITIAL PRODUCTION

Date of first production 6-16-81		Producing method (flowing, pumping, gas lift, etc.) Flowing			
RATE OF PRODUCTION PER 24 HOURS		Oil 9	Gas 627	Water 11	Gas-oil ratio 69,667/1
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold) Vented				Producing interval (s) 4732'-4694' 4687-4740	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Petrosil Exploration Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Beck

Gas

S 21 T 33 R 15 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Chase

2218'

Wabunsee

3131'

Topeka

3505'

Heebner

4048'

Lansing

4218'

Base of Kansas City

4660'

Massey

4718'

Cherokee

4790'

Mississippian

4853'

Kinderhook

5136'

Viola

5175'

Simpson

5308'

Arbuckle

5439'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

H. Timm, Production Manager

Title

July 7, 1981

Date

611081