

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


2-33-15W

Company - SINCLAIR-PRAIRIE OIL COMPANY
Farm - H. De Geor No. 1

SEC. 2 T. 33 R. 15W
SE SE NW

Total Depth. 5312
Comm. 7-13-48 Comp. 8-5-48
Shot or Treated.
Contractor. Harbar Drlg.
Issued. 3-26-49

County. Barber
KANSAS



CASING:

10 3/4" 695'
7" 2852'

Elevation. 1991 Ind.

Production. 5135 oil

Figures Indicate Bottom of Formations.

sand, gravel	80
red rock, shells	145
red rock, sand, shale	580
sand rock	601
pyrite	608
red rock, lime shells	702
red rock, shale	950
red rock, lime shells	1478
shale, sand, shells	1528
shale, shells	1733
salt, shale	1833
shale, shells	2198
anhydrite, shale	2288
lime, shale	2478
shale, shells	2593
lime, shale	3333
lime brkn	3408
lime	3473
shale, dolomite	3528
lime, shale	4383
lime	4393
lime cherty	4473
lime	4568
lime cherty	4843
lime	4873
lime, shale	5048
lime chert	5300
shale	5304
sand	5305
sand ?	5312
Total depth	

Tops: SJ

Lansing	4313
Mississippi lime	4870
Kinderhook	5058
Viola lime	5182
Simpson	5304