

2-33-15W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company - SINCLAIR OIL & GAS CO.
Farm - Hazel DeGeer No. 4

SEC. 2 T. 33 R. 15W
SE NW NW
990' fr N & W lines

Total Depth. 5337 PB 5297
Comm. 8-31-49 Comp. 9-26-49
Shot or Treated. 1000 gals acid.
Contractor. Harbar Drilling Co.
Issued. 12-17-49

County. Barber

KANSAS



Elevation. 2007 Ind.

Production. Pot. 3,000 bbls oil,
no water.

Figures indicate Bottom of Formations.

surface sand, shale	89
shells	184
shale	199
shells, shale	404
sand, shale	494
shale, shells	606
redbeds, shale, shells	1284
redbed, shells	1394
shale, shells	1494
lime, shale	1574
shale	2054
shale, shells	2094
lime	2609
lime, shale	3894
lime	4094
lime, shale	4214
lime	4239
shale, lime	4309
lime	4374
lime hrd	4404
lime	4624
lime hrd	4674
lime	4869
lime cherty	4924
lime	4974
lime, shale	5189
lime	5254
lime cherty	5279
lime	5322
lime, shale, sand	5337
Total Depth PB 5297	

Tops:

Kansas City	4340
Mississippi	4914
Viola	5209
Simpson shale	5323
Simpson sand	5325

No show at 5325'
Slight porosity 5222-24 and 5225-26'
Slight odor and stain 5238-43'.
Completed plugged back TD 5297' surface level.
Add 6' to all above measures for derrick
floor measure.
Perforated 26 holes 5238-5242 in Viola.
Drillers log corrected to surface level Meas.