

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


2-33-15W

Company - SINCLAIR OIL & GAS COMPANY
Farm - Hazel DeGeor No. 7

SEC. 2 T. 33 R. 15W
NW NE NW
330' Fr. NL, 990' Fr.
EL

Total Depth. 5284, PB 5250'
Comm. 2-27-50 Comp. 3-27-50
Shot or Treated.
Contractor.
Issued. 5-13-50

County. Barber
KANSAS



CASING:

10 3/4" osg @ 616' w/350 sx
7" osg. @ 5278' w/250 sx

Elevation. 2014 ft.

Production. Pot. 369 BO

Figures Indicate Bottom of Formations.

surface clay & sand	40
shale	435
redbed	1074
salt	1194
redbed & shale	1699
shale & shells	2109
shale & lime	2304
lime & shale	3044
shale & lime	3269
lime & shale	3479
shale & lime	3539
lime & shale	3659
lime-shale-sand	3769
shale & lime	3789
lime & shale	4034
shale & lime	4239
shale	4329
lime-shale	4354
shale	4369
lime & shale	4429
lime, hard	4466
lime & shale	4516
lime	4894
lime hard	4934
lime	4974
lime & chert	4994
lime	5119
lime & shale	5144
lime - Viola	5278
lime	5284
Total depth	

Tops:

Kansas City	4329
Mississippi	4918
Viola	5210

Remarks: Surface Level Measurements
(For Derrick Floor Meas. add 4')

Drilled cement & cleaned out to PB-TD
5250'; Perforated 29 holes in Viola
5243-5249' no show

Acid 1,000 gals., flowed 4 hrs. thru
3/4" choke 157 bbls. oil, no water.

State test 4/10/50 w/ BH Bomb flowed
18 hrs. thru 3/4" choke made indicated
cap. 1,146 bbls. oil, no water.

Will reacidize and test.

Acidized 3,000 gals. max press. 750# to
vac. Flowed 20 hrs. thru 1/4" choke,
2 1/2" tbg made 290 bbls. oil. 4/21/1950.
state test 8 hrs. flowing thru 19/32"
choke 2 1/2" tbg. made 122.96 bbls. oil
for a productivity of 369 bbls.