

2-33-15W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SINCLAIR OIL AND GAS CO.


SEC. 2 T. 33 R. 15W

FARM V. DeGeer "A" NO. 3

LOC. NW NW NE

330' fm Nth and West lines

TOTAL DEPTH 5278 PB 5239
 COMM. 7-23-50 COMP. 8-17-50
 SHOT OR TREATED
 CONTRACTOR Harbar Drlg. Co.
 ISSUED 11-25-50



CASING

3/4" 606' cem w/350 sx.
 7" 5274' cem w/250 sx.

ELEVATION 1979

PRODUCTION 11,000,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface level-DF 4½'

Derrick floor-Top Rotary bushing 2½'

Corrected to surface level.

sand, cly	90
redbed, shale, shells	845
redbed	1000
salt, shells	1053
dbed, shells	1212
shale, shells	1958
lime, shale	2083
lime	2409
lime brkn	2573
lime	2623
lime, shale	2968
lime brkn	3038
shale	3078
lime brkn, shale	3193
lime, shale	3668
sand	3723
shale	3800
lime, shale	3958
lime strks, shale	4133
lime brkn, shale	4208
lime	4273
lime, shale	4313
lime	4478
lime shale	4523
lime	4708
lime, shale	4750
lime	4900
lime, shale	4928
lime brkn	4963
lime	4978
lime shale	5083
lime	5153
lime, shale	5178
lime, chert	5188
lime dol.	5203

Perf. Viola 12 holes 5207-10' no show.
 Perf. Viola 12 holes 5198-5200' no show.
 Perf. Viola 12 holes 5193-5195' no show.
 Perf. Viola 12 holes 5191-5193' show gas,
 est. 200,000 cu ft. before tested.

lime	5223
lime, chert	5259
lime	5273
shale	5274
sand	5278
Total depth PB 5239	

Tops:
 Viola 5146
 Simpson shale 5264
 Simpson sand 5270
 Top cement plug not drilled 5239'.