

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-33-15W

Company- CHAMPLIN OIL & REFINING CO.
Farm- Brass No. 1

SEC. 4 T. 33 R. 15W
C NW SW

Total Depth. 5268'
Comm. 6-26-62 Comp. 7-19-62
Shot or Treated.
Contractor. Gabbert-Jones Drilling Co., Inc.
Issued. 12-1-62

County Barber
KANSAS



CASING:
20" 85' cem w/75 sx.
8 5/8" 277' cem w/250 sx.
5 1/2" 5222' cem w/110 sx.

Elevation. 1840' DF

Production. 11 BOPD, 14% WTR.

Figures Indicate Bottom of Formations.

red bed & gyp	85	w/specks of oil (nw) FP 0-62#,
red bed & sand	270	IBHP 1570#/30 min., FBHP 1410#/60 min.
red bed, shale & shells	930	
shale & shells	1675	
lime & shale	2570	
lime	2850	
shale & lime	3910	
lime & sandy shale	4035	
lime & shale	4195	
lime	4879	
lime & shale	4955	
lime	4986	
lime & shale	4998	
cherty lime & shale	5010	
lime	5047	
lime & shale	5076	
shale & sand	5123	
lime & sand	5141	
sand	5152	
shale & lime	5160	
lime	5260	
lime ?	5268	
Total Depth		

TOPS: LOG
Krider 2202
Fort Riley 2285
Florence 2408
Wreford 2551
Council Grove 2586
Elg 3812
Heebner 4000
Toronto 4062
Douglas Shale 4082
Lansing 4150
Base Kansas City 4632
Marmaton 4640
Cherokee 4738
Mississippi 4748
Kinderhook 4804
Woodford Shale 4918
Viola 4952
Simpson Sand 5090
Base Simpson Sand 5150
and Simpson Sand 5208
Arkuckle 5218

DST #1 2721-2850' op 90 min. Rec. 2100'
SW, FP 834-1110#, SIP 1116#/30 min. ---
1110#/60 min. Hydro pr. 1515#-1485#.
BHT 110 degrees F.

DST #2 4740-4783' Op 2 hrs. GTS 12"
(TSTM) Gd. blow of gas thruout. Rec. 60'
HG & OC mud, 180' mud cut oil, 90' free
oil, 160' HG & OCM, FP 50-160#, SIP 1760#/
30 min. -- 1750#/60 min., IHH 2490#
FMH 2480#, Grav. 47-48 degrees.

DST #3 4985-5010' Op 2 hrs. Fair blow
thruout. Rec. 340' gas in pipe & 90' sl. gcm